DRAINAGE IMPROVEMENTS

LOCATED IN

THE CITY OF ISLE OF PALMS, SOUTH CAROLINA

PREPARED FOR

CITY OF ISLE OF PALMS

PO BOX 508 ISLE OF PALMS, SC 29451 864-886-6428

PROJECT NOTES: 1. PROJECT OPERATOR: CITY OF ISLE OF PALMS P.O. BOX 508 ISLE OF PALMS, SC 29451 (864) 886-6428 2. ENGINEER: CIVIL SITE ENVIRONMENTAL (C.S. 668 MARINA DRIVE, SUITE B-1

CHARLESTON, SC 29492
PHONE: (843) 849-8945
FAX: (843) 849-8974

3. SURVEYOR:
SW&A SURVEYING
2093 EXECUTIVE HALL RD

2093 EXECUTIVE HALL RD
CHARLESTON, SC 29407
PHONE: (843) 795-9330
FAX: (843) 975-2007

4. PROJECT AREA OF DISTURBANCE:

SCDOT RIGHT OF WAY AREAS
CHARLESTON COUNTY MS4 AREAS
TOTAL

3.94 AC

5. WATER & SEWER CONTACT:
ISLE OF PALMS WATER AND SEWER COMMISSION
PO BOX 528
ISLE OF PALMS, SC 29451
PHONE: 843-886-6148

6. POWER: SCE&G
P.O. BOX 760
CHARLESTON, SC 29402
PHONE 843-576-8000

7. PHONE: AT&T
2600 MEETING STREET
CHARLESTON, SC 29423

PHONE: 843-745-6623

8. CABLE: COMCAST
4400 BELLE OAKS DRIVE
CHARLESTON, SC 29405

9. WILD DUNES RESORT:
5757 PALM BLVD.
ISLE OF PALMS, SC 29451
PHONE: 843-886-2314
CONTACT: SCOTT FERGUSON
DIRECTOR OF GOLF COURSE MAINTENANCE

10. WILD DUNES COMMUNITY ASSOCIATION:
6200 PALMETTO DR
ISLE OF PALMS, SC 29451
843-886-8847
CONTACT: DAVE KYNOSKI


11. PROJECT IS SITUATED IN FLOOD ZONES VE(16), AE (16), AE(15) AND AE(14)
COMMUNITY-PANEL #45019C 0561J & 45019C 0542J. EFFECTIVE DATE NOV. 17,2004

12. ALL ELEVATIONS REFER TO ABOVE MEAN SEA LEVEL (MSL) NGVD 29.

13. LATITUDE 32'48'08" LONGITUDE 79'44'26"

14. PER ARMY CORPS OF ENGINEERS DETERMINATION LETTER DATED JANUARY 28, 2013 (SAC# 2012-01136-2JY) EXISTING LAKES/STORMWATER PONDS SHOWN ON PLANS ARE WATERS OF THE UNITED STATES PERMITTED UNDER SECTION 402 OF THE CLEAN WATER ACT AND "...DEPARTMENT OF THE ARMY AUTHORIZATION WILL NOT BE REQUIRED FOR MECHANIZED LAND CLEARING, EXCAVATION, OR THE PLACEMENT OF DREDGED OR FILL MATERIAL ON THIS SITE."

		<u></u>	
SHEET	TITLE TO BE A SECOND OF THE SE		<u>REVISED</u>
SWP	GENERAL PROJECT NOTES & SWPPP		5/31/17
C100-100A	LIMITS OF DISTURBANCE		5/31/17
C101-107	EXISTING CONDITIONS		5/31/17
C200	PIPE & STRUCTURE CHARTS & DRAINAGE NOTES		5/31/17
C201-C207	DRAINAGE & EROSION CONTROL PLAN SHEETS		5/31/17
C300-C302	PIPE PROFILES		5/31/17
C400	SUNDIAL CIRCLE EASEMENT TREE REMOVAL		5/31/17
C401	SUMMARY SHEET OF EXISTING POND IMPACTS		5/31/17
CD-1	CONSTRUCTION DETAILS		5/31/17
CD-2	CONSTRUCTION DETAILS		5/31/17
CD-3	CONSTRUCTION DETAILS—WATER & SEWER DETAILS		5/31/17
L101	PLANTING PLAN		5/25/17
L102	PLANT SCHEDULE, NOTES, AND DETAILS		5/25/17



LOCATION MAP
NOT TO SCALE



CIVIL - SITE - ENVIRONMENTAL

668 MARINA DRIVE SUITE B-1 CHARLESTON, SOUTH CAROLINA 29492 843-849-8945




REVISIONS:
7/3/13 ADDED USACOE REFERENCE AND NOTATIONS FOR DED SHEETS 400 & 401
8/23/13 PER LOWE WILD DUNES, SCDOT, IOPWSC COMMEN 7/16/14 PER SCDOT COMMENTS
9/17/14 PER SCDHEC/ORCM COMMENTS
5/31/17 CONSTRUCTION BID SET


VER SHEET

COVER SH

DRAWN BY: JCM
FILE: 920-C000
SCALE: NONE

DATE: 6-28-13







668 MARINA DRIVE SUITE B-1 CHARLESTON, S.C. 2949

PHONE: (843) 849-8945 FAX: (843) 849-8974 EMAIL: CSE@CIVILSITEENV.COM

920-PH2
SHEET NUMBER

COOC

I. ALL AREAS OF THE SITE DISTURBED BY CONSTRUCTION ACTIVITY AND AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION; II. ALL STORMWATER CONVEYANCE SYSTEMS FOR ANY EVIDENCE OF, OR THE POTENTIAL FOR, POLLUTANTS ENTERING THESE SYSTEMS:

III. ALL BMPS IDENTIFIED IN THE OS-SWPPI IV. ALL DISCHARGE LOCATIONS TO ASCERTAIN WHETHER THE IMPLEMENTED BMPS ARE EFFECTIVE IN PREVENTING THE DISCHARGE OF SEDIMENT FROM THE SITE, WHERE DISCHARGE LOCATIONS ARE INACCESSIBLE, NEARBY DOWNSTREAM LOCATIONS MUST BE INSPECTED TO THE EXTENT THAT SUCH INSPECTIONS ARE PRACTICABLE: AND V. LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE MUST BE INSPECTED FOR EVIDENCE OF OFF-SITE SEDIMENT TRACKING.

IF INSPECTION RESPONSIBILITIES ARE NOT SHARED BETWEEN THE PRIMARY AND SECONDARY PERMITTEES, EACH SECONDARY PERMITTEE MUST PROVIDE THEIR OWN INSPECTIONS FOR THE PORTIONS OF THE SITE FOR WHICH THEIR COVERAGE INCLUDES.

B. FREQUENCY. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE. AN INSPECTION IS RECOMMENDED WITHIN 24 HOURS OF THE END OF A STORM EVENT OF 0.5 INCHES OR GREATER.

INSPECTION FREQUENCIES FOR PORTIONS OF THE CONSTRUCTION SITE THAT HAVE REACHED TEMPORARY OR FINAL STABILIZATION MAY BE REDUCED TO AT LEAST ONCE EVERY MONTH, AS LONG AS THE STABILIZATION IS MAINTAINED AND THERE IS NO ADDITIONAL DISTURBANCE IN THESE AREAS. ONCE A DEFINABLE AREA HAS REACHED FINAL STABILIZATION, YOU MAY MARK THIS ON YOUR ON-SITE SWPPP AND NO FURTHER INSPECTION REQUIREMENTS APPLY TO THAT PORTION OF THE SITE (E.G., LAND-DISTURBING ACTIVITIES AROUND ONE OF THREE BUILDINGS IN A COMPLEX ARE COMPLETED AND THE DISTURBED AREA HAS REACHED FINAL STABILIZATION, ONE MILE OF A ROADWAY OR PIPELINE PROJECT IS COMPLETED AND THE DISTURBED AREA HAS REACHED FINAL STABILIZATION, ETC). INSPECTION OF COMMON BMPS, SUCH AS SEDIMENT BASINS, SEDIMENT TRAPS, MAY BE REQUIRED TO RESUME IF AREAS THAT DRAIN TO THEM BECOME DISTURBED DURING FUTURE

C. RAIN GAUGE. PERMITTEES SHALL EITHER MAINTAIN AN ON-SITE RAIN GAUGE OR USE DATA FROM A CERTIFIED WEATHER RECORD (SUCH AS A PERSONAL WEATHER STATION OR AN AIRPORT) LOCATED WITHIN A REASONABLE PROXIMITY OF THE CONSTRUCTION SITE, TO RECORD RAINFALL RECÓRDS FROM ANY SIGNIFICANT RAINFALL EVENT, 0.5 INCHES OR GREATER. THESE RECORDED RAINFALL AMOUNTS MUST BE MAINTAINED IN A RAIN LOG LOCATED IN THE ON-SITE SWPPP. RAINFALL RECORDS FOR THE DAY OF AN INSPECTION AND ANY SIGNIFICANT RAINFALL EVENTS SINCE THE LAST INSPECTION MUST BE REPORTED ON EACH WEEKLY INSPECTION REPORT.

D. INSPECTOR QUALIFICATIONS. INSPECTIONS MUST BE CONDUCTED BY QUALIFIED PERSONNEL (PROVIDED BY THE PERMITTEE) AS OUTLINED BY THE FOLLOWING:

I. FOR PROJECTS THAT DISTURB MORE THAN 2 ACRES, "QUALIFIED PERSONNEL" MEANS A PERSON KNOWLEDGEABLE IN THE PRINCIPLES AND PRACTICE OF EROSION AND SEDIMENT CONTROLS WHO POSSESSES THE SKILLS TO ASSESS CONDITIONS AT THE CONSTRUCTION SITE THAT COULD IMPACT STORMWATER QUALITY AND TO ASSESS THE EFFECTIVENESS OF ANY BMPS SELECTED TO CONTROL THE QUALITY OF STORMWATER DISCHARGES FROM THE CONSTRUCTION SITE. THIS PERSON MUST BE EITHER THE PREPARER OF THE C-SWPPP OR AN INDIVIDUAL WHO IS UNDER THE DIRECT SUPERVISION OF THE PREPARER OF THE APPROVED C-SWPPP AND WHO MEETS THE REQUIREMENTS IN THIS PARAGRAPH OR AN INDIVIDUAL WHO HAS BEEN CERTIFIED THROUGH A CONSTRUCTION SITE INSPECTOR CERTIFICATION COURSE THAT HAS BEEN APPROVED BY DHEC. INSPECTIONS MAY ALSO BE CONDUCTED BY A PERSON WITH A REGISTRATION EQUIVALENT TO THE REGISTRATION OF THE PREPARER OF THE C-SWPPP AND WHO MEETS THE QUALIFICATIONS OF THIS PARAGRAPH OR AN INDIVIDUAL WHO IS UNDER THE DIRECT SUPERVISION OF THE PERSON WITH AN EQUIVALENT REGISTRATION AND WHO MEETS THE REQUIREMENTS IN THIS PARAGRAPH.

II. FOR PROJECTS THAT DISTURB 2 ACRES OR LESS, AND THAT ARE NOT PART OF A LARGER COMMON PLAN, THE PERMITTEE OR HIS DESIGNEE MAY PERFORM THESE INSPECTIONS PROVIDED THE PREPARER OF THE C-SWPPP OR SOMEONE WITH A REGISTRATION EQUIVALENT TO THAT OF THE PREPARER OF THE C-SWPPP EXPLAINS THE OS-SWPPP INCLUDING IMPLEMENTATION ALONG WITH THE INSPECTION REQUIREMENTS TO THE PERSON WHO WILL BE CONDUCTING THE INSPECTIONS. III. THE DEPARTMENT AND REGULATED MS4S RESERVES THE RIGHT TO REQUIRE THAT INSPECTIONS BE PERFORMED BY AN INSPECTOR MEETING THE REQUIREMENTS OF 4.2.E.I FOR CONSTRUCTION SITES

E. INSPECTION REPORTS. FOR EACH INSPECTION REQUIRED ABOVE, YOU MUST COMPLETE AN INSPECTION REPORT. AT A MINIMUM, THE INSPECTION REPORT MUST INCLUDE:

II. NAMES, TITLES, AND, IF NOT PREVIOUSLY GIVEN IN AN INSPECTION REPORT, THE QUALIFICATIONS OF PERSONNEL MAKING THE INSPECTION, UNLESS THOSE QUALIFICATIONS CHANGE; III. WEATHER INFORMATION FOR THE PERIOD SINCE THE LAST INSPECTION (OR SINCE COMMENCEMENT OF CONSTRUCTION ACTIVITY IF THE FIRST INSPECTION) INCLUDING A BEST ESTIMATE OF THE BEGINNING OF EACH STORM EVENT, DURATION OF EACH STORM EVENT, APPROXIMATE AMOUNT OF RAINFALL FOR EACH STORM EVENT (IN INCHES), AND WHETHER YOU KNOW IF ANY DISCHARGES OCCURRED. AT THE VERY LEAST, THE TOTAL RAINFALL (IN INCHES) SINCE THE TIME OF THE LAST INSPECTION MUST BE RECCRDED: IV. WEATHER INFORMATION AND A DESCRIPTION OF ANY DISCHARGES OCCURRING AT THE TIME OF

V. LOCATION(S) OF DISCHARGES OF SEDIMENT OR OTHER POLLUTANTS FROM THE SITE; VI. LOCATION(S) OF BMPS THAT NEED MAINTENANCE:

VII. LOCATION(S) OF BMPS THAT FAILED TO OPERATE AS DESIGNED OR PROVED INADEQUATE FOR A PARTICULAR LOCATION: VIII. LOCATION(S) WHERE ADDITIONAL BMPS ARE NEEDED THAT DID NOT EXIST AT THE TIME OF

INSPECTION: IX. CORRECTIVE ACTION REQUIRED INCLUDING ANY CHANGES TO THE OS-SWPPP NECESSARY AND IMPLEMENTATION DATES:

X. SITE NAME, OPERATOR NAME AND PERMIT NUMBER; AND XI. VERIFICATION THAT ALL BMPS AND STORMWATER CONTROLS IDENTIFIED IN THE OS-SWPPP HAVE BEEN INSTALLED AND ARE OPERATING AS DESIGNED.

F. MONTHLY REPORTS. DHEC MAY REQUIRE ON A CASE-BY-CASE BASIS THAT THE PERMITTEE SUBMIT A MONTHLY REPORT SUMMARIZING THE INSPECTIONS AT THE SITE AND ANY ASSOCIATED

G. INSPECTION RECORDS. A RECORD OF EACH INSPECTION AND OF ANY ACTIONS TAKEN IN ACCORDANCE WITH THIS SECTION MUST BE RETAINED AS PART OF THE ON-SITE SWPPP FOR AT LEAST THREE YEARS FROM THE DATE THAT PERMIT COVERAGE EXPIRES OR IS TERMINATED. THE QUALIFIED INSPECTOR, AS IDENTIFIED IN SECTION 4.2.E, MUST SIGN THE INSPECTION REPORT.

H. PRIMARY PERMITTEES. INSPECTORS EMPLOYED BY THE PRIMARY PERMITTEE RETAIN THE AUTHORITY TO INSPECT, REPORT, AND DOCUMENT AREAS OF THE CONSTRUCTION SITE THAT ARE UNDER DIRECT CONTROL OF THE SECONDARY PERMITTEE, BUT ONLY WHEN A LACK OF COMPLIANCE BY THE SECONDARY PERMITTEE INHIBITS THE PRIMARY PERMITTEE'S ABILITY TO MAINTAIN COMPLIANCE WITH THE OVERALL OS-SWPPP OR THIS PERMIT.

CONSTRUCTION MAINTENANCE PROCEDURES

ALL BMPS AND OTHER PROTECTIVE MEASURES IDENTIFIED IN THE OS-SWPPP MUST BE MAINTAINED IN EFFECTIVE OPERATING CONDITION. IF SITE INSPECTIONS REQUIRED BY SECTION 4.2 IDENTIFY BMPS THAT ARE NOT OPERATING EFFECTIVELY, MAINTENANCE MUST BE PERFORMED WITHIN SEVEN (7) CALENDAR DAYS, BEFORE THE NEXT INSPECTION, OR AS REASONABLY POSSIBLE, AND BEFORE THE NEXT STORM

EVENT WHENEVER PRACTICABLE TO MAINTAIN THE CONTINUED EFFECTIVENESS OF STORMWATER CONTROLS. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN USED INAPPROPRIATELY, OR INCORRECTLY, THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO CORRECT THE BMP WITHIN A TIME FRAME OF 48 HOURS OF IDENTIFICATION. IF EXISTING BMPS NEED TO BE MODIFIED OR IF ADDITIONAL BMPS ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF THIS PERMIT AND/OR SC'S WATER QUALITY STANDARDS, IMPLEMENTATION MUST BE COMPLETED BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE. IF IMPLEMENTATION BEFORE THE NEXT STORM EVENT IS IMPRACTICABLE, THE SITUATION MUST BE DOCUMENTED IN THE OS-SWPPP AND ALTERNATIVE BMPS MUST BE IMPLEMENTED AS SOON AS REASONABLY POSSIBLE. SEDIMENT FROM SEDIMENT TRAPS OR SEDIMENTATION BASINS MUST BE REMOVED AS INDICATED IN THE OS-SWPPP OR WHEN THE DESIGN CAPACITY HAS BEEN REDUCED BY 50 PERCENT, WHICH EVER OCCURS FIRST. SEDIMENT COLLECTED BY SILT FENCE, OR ANOTHER SEDIMENT CONTROL MEASURE, MUST BE REMOVED WHEN THE DEPOSITED SEDIMENT REACHES 1/3 OF THE HEIGHT OF THE ABOVE-GROUND PORTION OF THESE BMPS, OR BEFORE IT REACHES A LOWER HEIGHT BASED ON THE MANUFACTURER'S SPECIFICATIONS.

REQUIRED CERTIFICATIONS

COPIES OF ALL CERTIFICATIONS SHOULD BE KEPT WITH COPIES OF THE INSPECTION REPORTS, APPROPRIATE PERMTS, AND A COPY OF THE CONSTRUCTION PLANS. AT MINIMUM THE FOLLOWING CERTIFICATIONS SHOULD BE

1) OWNER CERTIFICATION

2) CONTRACTOR'S CERTIFICATION -ALL CONTRACTORS AND SUBCONTRACTORS IDENTIFIED IN THE PLAN TO PERFORM CONSTRUCTION RELATED WORK INTENDED TO DISTURB SOILS AT THE SITE THAT MAY AFFECT THE IMPLEMENTATION OF THE SWPPP BUT WHO WILL NOT BE CO-PERMITTEES MUST SIGN THE CONTRACTOR'S CERTIFICATION

3) CO-PERMITTEE CERTIFICATION -ALL CONTRACTORS AND SUBCONTRACTORS AND ANY OTHERS LISTED AS CO-PERMITTEES MUST SIGN A COPY OF THE CO-PERMITTEE CERTIFICATION

STANDARD NOTES:

1. IF NECESSARY, SLOPES, WHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.

2. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN FOURTEEN(14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW. WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS STABILIZATION MEASURES MUST BE INITIATED -WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.

3. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED ONCE CALENDAR EVERY WEEK. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN INAPPROPRIATELY, OR INCORRECTLY, THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO CORRECT THE BMP WITHIN 48 HOURS OF IDENTIFICATION.

4. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE SEDIMENT BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.

5. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION, ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.

6. THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED.

7. RESIDENTIAL SUBDIVISIONS REQUIRE EROSION CONTROL FEATURES FOR INFRASTRUCTURE AS WELL AS FOR INDIVIDUAL LOT CONSTRUCTION. INDIVIDUAL PROPERTY OWNERS SHALL FOLLOW THESE PLANS DURING CONSTRUCTION OR OBTAIN APPROVAL OF AN INDIVIDUAL PLAN IN ACCORDANCE WITH S.C REG. 72-300 ET SEQ. AND SCR100000.

8. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.

9. ALL WATERS OF THE STATE (WOS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FOOT BUFFER CAN'T BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WOS. A 10-FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WOS.

10. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.

11. A COPY OF THE SWPPP, INSPECTIONS RECORDS, AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED.

12. INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H: 1V OR GREATER) WHERE LAND-DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR DAYS.

13. MINIMIZE SOIL COMPACTION AND, UNLESS INFEASIBLE, PRESERVE TOPSOIL.

14. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT PROVIDES EQUIVALENT OR BETTER TREATMENT PRIOR TO DISCHARGE; 15. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE DISCHARGES ARE TO BE ROUTED THROUGH APPROPRIATE BMPS (SEDIMENT BASIN, FILTER BAG, ETC.).

16. THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED: WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE CONTROL WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS; FUELS, OILS, OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE; AND SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING.

17. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.

18. IF EXISTING BMPS NEED TO BE MODIFIED OR IF ADDITIONAL BMPS ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF THIS PERMIT AND/OR SCS WATER QUALITY STANDARDS, IMPLEMENTATION MUST BE COMPLETED BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE. IF IMPLEMENTATION BEFORE THE NEXT STORM EVENT IS IMPRACTICABLE, THE SITUATION MUST BE DOCUMENTED IN THE SWPPP AND ALTERNATIVE BMPS MUST BE IMPLEMENTED AS SOON AS REASONABLY POSSIBLE.

19. A PRE-CONSTRUCTION CONFERENCE MUST BE HELD FOR EACH CONSTRUCTION SITE WITH AN APPROVED ON-SITE SWPPP PRIOR TO THE IMPLEMENTATION OF CONSTRUCTION ACTIVITIES. FOR NON-LINEAR PROJECTS THAT DISTURB 10 ACRES OR MORE THIS CONFERENCE MUST BE HELD ON-SITE UNLESS THE DEPARTMENT HAS APPROVED OTHERWISE

POTENTIAL POLLUTANTS AND SOURCES OF CONTAMINATION

1) SIGNIFICANT MATERIAL INVENTORY POLLUTANTS FROM CLEARING, GRADING, EXCAVATION, FILL ACTIVITIES, BUILDING CONSTRUCTION, AND PAVING ACTIVITIES HAVE THE POTENTIAL TO BE PRESENT IN STORMWATER RUNOFF FROM THE CONSTRUCTION SITE. TABLE 1 INCLUDES INFORMATION ON MATERIAL TYPES, CHEMICAL AND PHYSICAL

2) POTENTIAL AREAS FOR STORMWATER CONTAMINATION

THE FOLLOWING POTENTIAL SOURCES OF STORM WATER CONTAMINATION WERE IDENTIFIED: 1) CLEARED AREAS

2) BUILDING CONSTRUCTION AREAS 3) CONSTRUCTION SITE ENTRANCES 4) ASPHALT PARKING CONSTRUCTION AREAS

TABLE 2 LISTS POTENTIAL STORM WATER POLLUTANTS FROM CONSTRUCTION

3) SUMMARY OF AVAILABLE STORM WATER SAMPLING DATA NO STORM WATER SAMPLING DATA IS AVAILABLE FOR THE SITE.

4) LITTER, CONSTRUCTION DEBRIS, CONCRETE WASHOUT, OILS, FUELS AND BUILDING PRODUCTS EXPOSED TO STORMWATER SHALL BE PREVENTED FORM BECOMING A POLLUTANT SOURCE IN STORMWATER DISCHARGES.

ALLOWABLE NON-STORM WATER DISCHARGES

THE FOLLOWING ARE ALLOWABLE NON-STORM WATER DISCHARGES:

1) DISCHARGES FROM FIRE FIGHTING ACTIVITIES 2) FIRE HYDRANT FLUSHINGS 3) WATERS USED TO WASH VEHICLES WHERE DETERGENTS ARE NOT USED 4) WATER USED TO CONTROL DUST IN ACCORDANCE WITH SCR100000

5) POTABLE WATER INCLUDING UNCONTAMINATED WATER LINE FLUSHINGS 6) ROUTINE EXTERNAL BUILDING WAS DOWN THAT DOES NOT USE 7) PAVEMENT WASH WATERS WHERE SPILLS OR LEAKS OF TOXIC OR HAZARDOUS MATERIALS HAVE NOT OCCURRED (UNLESS ALL SPILLED MATERIAL HAS BEEN REMOVED) AND WHERE DETERGENTS ARE NOT

8) UNCONTAMINATED AIR CONDITIONS OR COMPRESSOR CONDENSATE 9) UNCONTAMINATED GROUND WATER OR SPRING WATER 10) FOUNDATION OR FOOTING DRAINS WHERE FLOWS ARE NOT CONTAMINATED WITH PROCESS MATERIALS SUCH AS SOLVENTS 11)UNCONTAMINATED EXCAVATION DEWATERING 12)LANDSCAPE IRRIGATION

THE NON-STORM WATER DISCHARGES LISTED ABOVE SHALL BE ROUTED SUCH THAT THEY DO NOT CAUSE UNNECESSARY EROSION OR SEDIMENT DISCHARCE FROM THE SITE. IF THESE DISCHARGE HAVE THE POTENTIAL TO CARRY SEDIMENT, THE DISCHARGE SHALL BE ROUTED THROUGH AN APPROPRIATE BMP TO ALLOW THE SEDIMENT TO SETTLE OUT BEFORE LEAVING

PRE CONSTRUCTION CONFERENCE

PROJECTS THAT DISTURB 10 ACRES OR MORE A PRE-CONSTRUCTION CONFERENCE MUST BE CONDUCTED WITH EACH CO-PERMITTEE, AND CONTRACTOR WHO IS NOT A CO-PERMITTEE, IN PERSON AT THE SITE PRIOR TO THAT CO-PERMITTEE OR CONTRACTOR PERFORMING CONSTRUCTION RELATED WORK INTENDED TO DISTURB SOILS AT THE SITE THAT MAY AFFECT THE IMPLEMENTATION OF THE SWPPP UNLESS IT IS JUSTIFIED IN THE SWPPP AND APPROVED BY THE SCDHEC/OCRM TO CONDUCT THE CONFERENCE OFF-SITE. THIS PRECONSTRUCTION CONFERENCE CAN BE WITH ALL CONTRACTORS OR THE PRE-CONFERENCE MAY BE CONDUCTED SEPARATELY WITH ONE OR MORE CONTRACTORS PRESENT SO THAT ALL CONTRACTORS WHO PERFORM LAND DISTURBING ACTIVITY OR CONSTRUCTION ACTIVITY ARE AWARE OF THE REQUIREMENTS OF THE SWPPP BEFORE THEY START CONSTRUCTION.

SEQUENCE OF EVENTS) PRECONSTRUCTION MEETING 2) INSTALL EROSION CONTROL

& TREE PROTECTION) INSTALL STORM DRAINAGE LINES

4) LANDSCAPE/STABILIZE ALL DISTURBED AREAS AS LINEAR WORK IS COMPLETED 5) REMOVE EROSION CONTROLS ONCE

REVISION TO SWPPP AS RESULT OF INSPECTIONS

THE CHANGES, AND SIGNATURES OF THE INSPECTOR AND

THE SWPPP SHOULD BE INCLUDED ON THE NEXT MONTHLY

SUBMITTAL TO SCDHEC.

CONTROLS

PROCESS FOR UPDATING SWPPP

CONTRACTOR CONDUCTING WORK ON THE SITE.

2) DATES OF MAJOR GRADING ACTIVITIES

THOSE AREAS THAT ARE STABILIZED.

Know what's **below**.

Call before you dig.

RECORDING OF MAJOR ACTIVITIES

KEPT. THESE RECORDS SHOULD INCLUDE:

PERMANENTLY CEASES

REVISIONS TO THE SWPPP AS A RESULT OF INSPECTIONS

SHALL BE DOCUMENTED WITH REQUIRED CHANGES, REASON FOR

OPERATOR RECOMMENDING/INITIATING REVISIONS. REVISIONS TO

THIS SWPPP SHALL BE UPDATED WHEN CHANGES NEED TO BE MADE DURING THE CONSTRUCTION PROCESS INCLUDING THE

ADDITION OF ANY CONTROL MEASURES OR PROCEDURES. THESE

CHANGES WILL BE MADE BY THE APPROPRIATE PERSONNEL AND

RECORDS OF MAJOR CONSTRUCTION EVENTS SHOULD BE

4) DATES WHEN CONSTRUCTION ACTIVITY TEMPORARILY OR

5) DATES WHEN STABILIZATION IS INITIATED AND LOCATION OF

CHANGES SHOULD BE DISTRIBUTED TO EACH OPERATOR AND

1) DATE OF INSTALLATION OF SEDIMENT AND EROSION

DATES OF INITIATION OF BUILDING CONSTRUCTION

6) SUBMIT NOTICE OF TERMINATION (NOT)

CONTRACTOR CERTIFICATIONS AND CO-PERMITTEE STATUS

PER NPDES GENERAL PERMIT FOR STORMWATER DISCHARGES FROM LARGE AND SMALL CONSTRUCTION ACTIVITIES (SCR100000, EFFECTIVE JAN 1, 2013)":

"1. THE OWNER OF A PROJECT, AS THE APPLICANT FOR THE NPDES PERMIT, IS RESPONSIBLE FOR COMPLIANCE WITH ALL THE TERMS AND CONDITIONS OF THIS PERMIT AND THE SWPPP. THE OWNER MAY RELY ON OTHER PERSONS TO ASSIST IN COMPLIANCE WITH THIS PERMIT AND THE SWPPP. AS SUCH, THE PROJECT OWNER AND CONTRACTORS AND SUBCONTRACTORS WHO WILL CONDUCT CONSTRUCTION ACTIVITIES INTENDED TO DISTURB SOILS MAY ELECT TO BE CO-PERMITTEES. FURTHER, ALL CONTRACTORS WHO WILL CONDUCT CONSTRUCTION RELATED WORK INTENDED TO DISTURB SOILS AT THE SITE THAT MAY AFFECT IMPLEMENTATION OF THE SWPP REGARDLESS OF WHETHER OR NOT THEY ARE CO-PERMITTEES, MUST BE LISTED IN THE SWPPP AND ATTEND A PRE-CONSTRUCTION CONFERENCE BEFORE THEY CAN CONDUCT CONSTRUCTION ACTIVITY AT THE SITE.

2. ALL CONTRACTORS AND SUBCONTRACTORS IDENTIFIED IN THE PLAN AS CO-PERMITTEES MUST SIGN A COPY OF THE CERTIFICATION STATEMENT GIVEN BELOW: "I CERTIFY BY MY SIGNATURE BELOW THAT: A) FOR SITES THAT DISTURB 10 OR MORE ACRES, I PARTICIPATED IN A PRE-CONSTRUCTION CONFERENCE ONSITE OR, WHEN ALLOWED, OFFSITE WITH THE INDIVIDUAL WHO IS RESPONSIBLE FOR THE OPERATIONAL CONTROL OF THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP); AND B) I ACCEPT THE TERMS AND CONDITIONS OF SWPPP AS REQUIRED BY THE GENERAL NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES PERMIT NUMBER SCR100000) ISSUED TO THE OWNER/OPERATOR OF THE CONSTRUCTION ACTIVITY FOR WHICH I HAVE BEEN CONTRACTED TO PERFORM CONSTRUCTION RELATED PROFESSIONAL SERVICES. FURTHER, BY MY SIGNATURE BELOW, I UNDERSTAND THAT I AM BECOMING A CO-PERMITTEE WITH THE OWNER/OPERATOR AND OTHER CONTRACTORS THAT HAVE BECOME CO-PERMITTEES TO THE GENERAL NPDES PERMIT ISSUED TO THE OWNER/OPERATOR OF THE FACILITY FOR WHICH I HAVE BEEN CONTRACTED TO PERFORM PROFESSIONAL CONSTRUCTION SERVICES. AS A CO-PERMITTEE, I UNDERSTAND THAT I, AND MY COMPANY, AS THE CASE MAY BE, AM LEGALLY ACCOUNTABLE TO THE SC DEPARTMENT OF HEALTH AND ENVIRONMENTAL CONTROL (DHEC), UNDER THE AUTHORITIES OF THE CWA AND THE SC POLLUTION CONTROL ACT, TO ENSURE COMPLIANCE WITH THE TERMS AND CONDITIONS OF THE SWPPP. I ALSO UNDERSTAND THAT DHEC ENFORCEMENT ACTIONS MAY BE TAKEN AGAINST ANY SPECIFIC CO-PERMITTEE OR COMBINATION OF CO-PERMITTEES IF THE TERMS AND CONDITIONS OF THE SWPPP ARE NOT MET. THEREFORE, HAVING UNDERSTOOD THE ABOVE INFORMATION, I AM SIGNING THIS CERTIFICATION AND AM RECEIVING CO-PERMITTEE STATUS TO THE AFOREMENTIONED GENERAL NPDES PERMIT."

3. ALL CONTRACTORS AND SUBCONTRACTORS IDENTIFIED IN THE PLAN TO PERFORM CONSTRUCTION RELATED WORK INTENDED TO DISTURB SOILS AT THE SITE THAT MAY AFFECT THE IMPLEMENTATION OF THE SWPPP BUT WHO WILL NOT BE CO-PERMITTEES MUST SIGN THE CERTIFICATION STATEMENT GIVEN BELOW: "I CERTIFY BY MY SIGNATURE BELOW THAT: A) FOR SITES THAT DISTURB 10 OR MORE ACRES, I PARTICIPATED IN A PRE-CONSTRUCTION CONFERENCE ONSITE OR, WHEN ALLOWED, OFFSITE WITH THE INDIVIDUAL WHO IS RESPONSIBLE FOR THE OPERATIONAL CONTROL OF THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP); AND B) I UNDERSTAND THE TERMS AND CONDITIONS OF SWPPP AS REQUIRED BY THE GENERAL NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM PERMIT (NPDES PERMIT NUMBER SCR100000) ISSUED TO THE OWNER/OPERATOR OF THE CONSTRUCTION ACTIVITY FOR WHICH I HAVE BEEN CONTRACTED TO PERFORM CONSTRUCTION RELATED PROFESSIONAL SERVICES. I UNDERSTAND THAT I, AND MY COMPANY, AS THE CASE MAY BE, MAY BE LEGALLY ACCOUNTABLE TO THE SC DEPARTMENT OF HEALTH AND ENVIRONMENTAL CONTROL (DHEC), UNDER THE AUTHORITIES OF THE CWA AND THE SC POLLUTION CONTROL ACT, TO ENSURE COMPLIANCE WITH THE TERMS AND CONDITIONS OF THE SWPPP.

4. THE DATE OF THE SIGNATURE, THE TITLE OF THE PERSON PROVIDING THE SIGNATURE, AND THE NAP ADDRESS, AND TELEPHONE NUMBER OF THE CONTRACTED FIRM, SHALL ALSO BE PROVIDED. IN THE EVENT THE OWNER AMENDS THE SWPPP, SUCH AMENDMENTS SHOULD BE INCORPORATED TO THE PLAN AND THE CONTRACTORS AND SUBCONTRACTORS SHOULD ACKNOWLEDGE BY SIGNATURE. CO-PERMITTEES WHO HAVE COMPLETED THEIR WORK PRIOR TO THE AMENDMENTS DO NOT HAVE TO SIGN THE AMENDMENTS.

5. THE SIGNATORY REQUIREMENTS OF \$122.22 OF SOUTH CAROLINA REGULATION 61-9 (SEE APPENDIX C OF THIS PERMIT) ARE APPLICABLE TO EACH CONTRACTED ENTITY THAT MUST SIGN ONE OF THE CONTRACTOR'S CERTIFICATION STATEMENTS. UPON SIGNING THE CO-PEMITTEE CERTIFICATION, THE CONTRACTOR IS A COPERMITTEE AND BECOMES ACCOUNTABLE TO DHEC TO ENSURE THE TERMS AND CONDITIONS OF THIS PERMIT ARE IMPLEMENTED. ALL CO-PERMITTEES ARE SUBJECT TO DHEC ENFORCEMENT ACTIONS IF PERMIT CONDITIONS ARE NOT MET. ENFORCEMENT ACTIONS MAY BE TAKEN AGAINST ANY SPECIFIC CO-PERMITTEE OR COMBINATION OF CO-PERMITTEE, WITH CONSIDERATION GIVEN TO THE PARTY RESPONSIBLE FOR THE VIOLATION. THE OWNER/OPERATOR SUBMITTING THE NOI SHALL RETAIN ALL CONTRACTOR CERTIFICATIONS FOR AT LEAST THREE YEARS AFTER A CONTRACTOR HAS COMPLETED WORK AT THE SITE. CONTRACTORS WHO SIGN THE CERTIFICATION FOR BEING A CO-PERMITTEE MAY BE LIABLE TO DHEC ENFORCEMENT ACTIONS RELATED TO THEIR WORK AT THE SITE. ALL CERTIFICATIONS MUST BE INCLUDED IN THE STORM WATER POLLUTION PREVENTION PLAN.

6. COPIES OF ALL CONTRACTOR CERTIFICATIONS AND A COPY OF THIS PERMIT SHALL BE KEPT WITH THE SWPPP. FOR CONSTRUCTION SITES THAT DISTURB 10 ACRES OR MORE, THE FIRST MONTHLY REPORT OR COPIES OF THE FIRST MONTH'S INSPECTION FORMS (REFER TO PART 4.2) SUBMITTED BY THE OWNER/OPERATOR TO THE DEPARTMENT AFTER CONSTRUCTION BEGINS ON THE FACILITY MUST INCLUDE THE ORIGINAL AND ONE COPY OF ALL CO-PERMITTEE AND OTHER CONTRACTOR CERTIFICATIONS. IF ADDITIONAL CO-PERMITTEES OR OTHER CONTRACTORS ARE ADDED LATER ON, THE ORIGINAL AND ONE COPY OF THE ADDITIONAL CO-PERMITTEE OR CONTRACTOR CERTIFICATIONS MUST BE SUBMITTED ALONG WITH THE MONTHLY REPORTS OR COPIES OF THE INSPECTION FORMS SUBMITTED AFTER THE SIGNING OF THE CERTIFICATION. FOR CONSTRUCTION SITES THAT COVERED BY THIS PERMIT SHALL MA ALL CONTRACTOR CERTIFICATIONS AVAILABLE TO DHEC UPON REQUEST. THE DEPARTMENT MAY ON A CASEBY-CASE BASIS REQUIRE THE SUBMITTAL OF THE CO-PERMITTEE AND OTHER CONTRACTOR CERTIFICATIONS."

> CONTRACTOR SHALL BE REQUIRED TO HAVE PROPOSED ROUTE STAKED, ALL **UTILITY CROSSINGS VERTICALLY** LOCATED, AND A WALK THROUGH CONDUCTED WITH ENGINEER PRIOR TO INITIATION OF CONSTRUCTION.

TABLE 1. SEEDING SCHEDULE

SPECIES

TEMPORARY SEEDING

	SANDY, DROUG	HTY S	ITES										
ROWNTOP MILLET	40 LBS/AC		T	7/11/11/1				rusun	SALSALIA	a		Π	Т
RYE, GRAIN"	56 LBS/AC					T			<u> </u>	11111 1111		0.90i9 10180	
YEGRASS	50 LBS/AC					1	†			annun,	20000	1500000	5'111112 A
WELL D	PRAINED, CLAYEY	//LOAN	WEY SI	TES	<u> </u>			<u> </u>		_			Ε
ROWNTOP MILLET OR	40 100 (40						T			Γ		Γ	Т
APANESE MILLET	40 LBS/AC			7777.	zunian	2000000	411111111111111111111111111111111111111		'1111111111111111111111111111111111111	1 '		'	
RYE, GRAIN OR "	56 LBS/AC	L					 	\vdash		 	 	\vdash	
ATS	75 LBS/AC	Mashiin	o WWW.Wiin.		'					ummir)	UNIVIII I	111111111111111111111111111111111111111	Willia h
YEGRASS	50 LBS/AC	W.W.(I)		.y:mm	01111					anas a	1111111 KB	111111-1111	
			·			<u> </u>	<u></u>	<u></u>	<u> </u>	L	<u> </u>		
	PERMANENT S	EEDIN	G										
PECIES	LBS/AC	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	ОСТ	NOV	DEC
	SANDY, DROUGH	HTY SI	TES							<u></u>			<u> </u>
ROWNTOP MILLET	10 LBS/AC												
AHIAGRASS	40 LBS/AC			Wille.	ummi.	HAMANI.	7/////////////////////////////////////	YNNIN IN			i	1 1	
ROWNTOP MILLET	10 LBS/AC				T								
AHIAGRASS	30 LBS/AC			7/1/20	uman n	911111111111111111111111111111111111111	111111111111			1		ıJ	1
ERICEA LESPEDEZA	40 LBS/AC			1 1	1 1			, , ,	, J		, ·	i	
ROWNTOP MILLET	10 LBS/AC												
TANTIC COASTAL	15 LBS/AC		1 1	Sun		1111:1111/h		, ,			. 1	ı J	1
ANICGRASS	PLS			1 1]	l
ROWNTOP MILLET	10 LBS/AC												
VITCHGRASS	8 LBS/AC			,	. 1								ĺ
LAMO)	PLS				<i>11117161167</i>		W. HHA						l
TTLE BLUESTEM	4 LBS/AC				. 1	. I	_	- 1	1			1	
RICEA LESPEDEZA	20 LBS/AC												İ
OWNTOP MILLET	10 LBS/AC								\neg	$\overline{}$	_	-	

LBS/AC JAN FEB MAR APR MAY JUN JUL AUG SEP OCT NOV DEC

WEEPING LOVEGRASS 8 LBS/AC WELL DRAINED, CLAYEY/LOAMEY SITES BROWNTOP MILLET 10 LBS/AC BAHIAGRASS 40 LBS/AC "RYE,GRAIN" 10 LBS/AC BAHIAGRASS 40 LBS/AC "CLOVER, CRIMSON" 5 LBS/AC BROWNTOP MILLET 10 LBS/AC 30 LBS/AC SERICEA LESPEDEZA 40 LBS/AC BROWNTOP MILLET 10 LBS/AC BERMUDA, COMMON' 10 LBS/AC SERICEA LESPEDEZA 40 LBS/AC BROWNTOP MILLET 10 LBS/AC BERMUDA, COMMON" 12 LBS/AC KOBE LESPEDEZA 10 LBS/AC BROWNTOP MILLET 10 LBS/AC BAHIAGRASS 20 LBS/AC "BERMUDA, COMMON" 6 LBS/AC SERICEA LESPEDEZA 40 LBS/AC BROWNTOP MILLET 10 LBS/AC SWITCHGRASS 8 LBS/AC LITTLE BLUESTEM 3 LBS/AC **INDIANGRASS** 3 LBS/AC PLS

NOTE: SEEDING CHART APPLIES ONLY TO AREAS INDICATED ON PLANS WHERE SOD OR OTHER LANDSCAPE RESTORATION IS NOT REQUIRED. GOLF COURSE REPAIRS SHALL BE PER WILD DUNES GOLF COURSE SPECIFICATIONS.

ADDITIONAL PRACTICES TO MINIMIZE STORM WATER CONTAMINATION

THE FOLLOWING ADDITIONAL MEASURES WILL BE FOLLOWED TO MINIMIZE POTENTIAL CONTAMINATION OF STORM WATER DISCHARGES:

1) ALL VEHICLES ON SITE WILL BE MONITORED FOR LEAKS AND RECEIVE REGULAR PREVENTIVE MAINTENANCE TO REDUCE THE CHANCE OF LEAKAGE 2) PETROLEUM PRODUCTS WILL BE STORED IN TIGHTLY SEALED CONTAINERS WHICH ARE CLEARLY LABELED AND SHALL BE STORED IN APPROPRIATE LOCATIONS TO PREVENT UNAUTHORIZED ACCESS. 3) SPILL KITS WILL BE INCLUDED WITH ALL FUELING SOURCES AND MAINTENANCE ACTIVITIES. ALL SPILLS WILL BE CLEANED UP IMMEDIATELY UPON DISCOVERY.

4) ANY PETROLEUM OR ASPHALT SUBSTANCES USED ONSITE WILL BE APPLIED ACCORDING TO THE MANUFACTURER'S RECOMMENDATION. 5) SANITARY WASTE WILL BE COLLECTED FROM PORTABLE UNITS REGULARLY TO AVOID OVERFILLING. 6) COVERED DUMPSTERS WILL BE USED FOR TRASH DISPOSAL. HAZARDOUS WASTE

MATERIALS SHOULD BE DISPOSED OF PROPERLY AND SHOULD NOT BE DISPOSED OF WITH TRASH AND OTHER CONSTRUCTION DEBRIS. SITE SHOULD BE POLICED MEEKLY TO CLEAN UP TRASH AND DEBRIS THAT MAY HAVE BEEN BLOWN ACROSS THE SITE. IF FORECAST STORMS ARE PREDICTED TO HAVE HIGH WINDS, APPROPRIATE MEASURES SHOULD BE TAKEN TO SECURE DUMPSTERS AND CONSTRUCTION DEBRIS TO PREVENT MATERIALS FROM BEING BLOWN FROM SITE.) ALL PAINT CONTAINERS AND CURING COMPOUNDS WILL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE. EXCESS PAINT WILL NOT BE DISCHARGED O THE STORM SYSTEM, BUT WILL BE PROPERLY DISPOSED OF ACCORDING THE MANUFACTURER'S INSTRUCTIONS AND IN ACCORDANCE WITH ALL FEDERAL, STATE, 8) MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN A

CENTRAL, ACCESSIBLE LOCATION. EQUIPMENT WILL INCLUDE, BUT NOT BE LIMITED TO, BROOMS, DUST PANS, MOPS, RAGS, GLOVES, GOGGLES, KITTY LITTER, SAND, SAW DUST, AND PLASTIC AND METAL TRASH CONTAINERS. 9) WHEN TESTING/CLEANING OF WATER SUPPLY LINES, THE DISCHARGE FROM THE TESTED PIPE WILL BE COLLECTED AND CONVEYED TO A COMPLETED STORM WATER SYSTEM FOR CONVEYANCE TO THE MAIN STORM WATER RETENTION POND OR TREATMENT SYSTEM ONSITE. 10) THE PAVED STREETS ADJACENT TO THE SITE ENTRANCE WILL BE SWEPT WEEKLY

(OR MORE FREQUENTLY) TO REMOVE EXCESS MUD, DIRT, OR ROCK TRACKED FROM

11) DUMP TRUCKS HAULING MATERIAL FROM THE CONSTRUCTION SITE WILL BE COVERED WITH A TARPAULIN. 12) CONSTRUCTION ENTRANCE SHALL BE PERIODICALLY REFRESHED WITH FRESH STONE TO ENSURE PROPER FUNCTIONING OF CONSTRUCTION ENTRANCE. 13) LITTER, CONSTRUCTION DEBRIS, CONCRETE WASHOUT, OILS, FUELS AND BUILDING PRODUCTS EXPOSED TO STORMWATER SHALL BE PREVENTED FROM BECOMING

CONSTRUCTION STAGING AREAS (INCLUDING BUILDING CONSTRUCTION)

A POLLUTANT SOURCE IN STORMWATER DISCHARGES.

THE MEASURES LISTED APPLY FOR ALL CONSTRUCTION STAGING AREAS. ADDITIONALLY, STAGING AREAS SHOULD BE APPROPRIATELY SECURED TO PREVENT UNAUTHORIZED ACCESS TO STORED HAZARDOUS MATERIALS AND CONSTRUCTION WASTE AND DEBRIS. IF BUILDING CONSTRUCTION TAKES PLACE AFTER BASE COURSE HAS BEEN PLACED (OR AFTER ASPHALT COURSE HAS BEEN PLACED) INLET PROTECTION SHOULD BE PLACED AROUND ANY INLETS TO WHICH STORM WATER FROM STAGING AREA WILL DRAIN. INLET PROTECTION SHOULD BE PROTECTED FROM TRAFFIC WHICH MAY RUN OVER OR DISTURB PROTECTION MEASURES.


TABLE 2. POTENTIAL STORMWATE		
	CHEMICAL/PHYSICAL DESCRIPTION	POTENTIAL STORMWATER POLLUTANT
PESTICIDES (INSECTICIDES, FUNGICIDES,	VARIOUS COLORED TO COLORLESS LIQUID,	CHLORINATED HYDROCARBONS,
HERBICIDES, RODENTICIDES)	POWDER, PELLETS, OR GRAINS	ORGANOPHOSPHATES, CARBAMATES,
		ARSENIC
FERTILIZER	LIQUID OR SOLID GRAINS	NITROGEN, PHOSPHOROUS
PLASTER	WHITE GRANULES OR POWDER	CALCIUM SULPHATE, CALCIUM
		CARBONATE, SULFURIC ACID
CLEANING SOLVENTS	COLORLESS, BLUE, OR YELLOW-GREEN	PERCHLOROETHYLENE, METHYLENE
	LIQUID	CHLORIDE, TRICHLOROETHYLENE,
		PETROLEUM DISTILLATES
ASPHALT	BLACK SOLID	OIL, PETROLEUM DISTILLATES
CONCRETE	WHITE SOLID	LIMESTONE, SAND
GLUE, ADHESIVES	WHITE OR YELLOW LIQUID	POLYMERS, EPOXIES
PAINTS	VARIOUS COLORED LIQUID	METAL OXIDES, STODDARD SOLVENT,
		TALC, CALCIUM CARBONATE, ARSENIC
CURING COMPOUNDS	CREAMY WHITE LIQUID	NAPHTHA
WASTEWATER FROM CONSTRUCTION	WATER	SOIL, OIL & GREASE, SOLIDS
EQUIPMENT WASHING		0.00, 0.00, 0.00,
WOOD PRESERVATIVES	CLEAR AMBER OR DARK BROWN LIQUID	STODDARD SOLVENT, PETROLEUM
		DISTILLATES, ARSENIC, COPPER.
		CHROMIUM
TYDRAULIC OIL/FLUIDS	BROWN OILY PETROLEUM HYDROCARBON	MINERAL OIL
GASOLINE	COLORLESS, PALE BROWN OR PINK	BENZENE, ETHYL BENZENE, TOLUENE.
	PETROLEUM HYDROCARBON	XYLENE, MTBE
DIESEL FUEL	CLEAR, BLUE-GREEN TO YELLOW LIQUID	PETROLEUM DISTILLATE, OIL & GREASE
	The state of the s	
(EROSENE	PALE YELLOW LIQUID PETROLEUM	NAPHTHALENE, XYLENES
	HYDROCARBON	COAL OIL, PETROLEUM DISTILLATES
NTIFREEZE/COOLANT	CLEAR GREEN/YELLOW LIQUID	ETIMENE OLYGOL PROPERTY
	SELLIN OFFEIA LEFTOM FIGURE	ETHYLENE GLYCOL, PROPYLENE GLYCOL
ROSION	SOLID PARTICLES	HEAVY METALS (COPPER, LEAD, ZINC)
IOTE: THIS LIST CONTAINS POSSIBLE CON		SOIL, SEDIMENT


SPILL AND CONTAMINANT AND MATERIALS USED TO CLEAN UP SPILLS SHOULD BE DISPOSED OF IN AN APPROPRIATE MANNER.

0 DRAIN,

DRAWN BY: JCM

FILE: C100 SCALE: NONE DATE: 6-28-13









668 MARINA DRIVE SUITE B-1 CHARLESTON, S.C. 2949


PHONE: (843) 849-8945 FAX: (843) 849-8974 CSE@CIVILSITEENV.COM


CSE JOB NUMBER 920-PH2


SHEET NUMBER


















S:\920-Ph2\920-PH2-Dwg\Construction Drawings



			PIPE	CHART				
FROM	TO	LENGTH	DIAMETER		SLOPE	I.E.	I.E.	10 YR
		(FT)	(IN)	TYPE	%	(FROM)	(TD)	VEL
JB81	JB80	26	36	□-RCP	0.27%	1.97	2.04	5.37
JB80	JB79	57	36	□-RCP	0.30%	2.04	2.21	3,50
JB79	JB78	44	36	D-RCP	1.48%	2.21	2.34	3.27
JB78 JB77	JB77 CS76	67 108	36	D-RCP	0.29%	2.86	3.00	3.50
JB//	US/6	100	36	D-RCP	0.37%	3.00	3,40	4,41
LAKE3	JB75	112	54	D-RCP	0.28%	2.50	2.15	1.74
JB75	LAKE1	169	54	D-RCP	0.30%	2.15	1.69	1.42
0270	Crittee	107	. 01	L KO	0.00%	L.13	1.07	21-7-
LAKE2	JB73	137	42	□-RCP	0.28%	3.00	2.62	4,95
JB73	JB74	85	42	U-RCP	0.30%	2.62	2.34	3,48
JB74	LAKE3	215	42	□-RCP	0.29%	2.34	1.68	2.93
		·						
LAKE5	LAKE6	80	36	□-RCP	0.50%	3.00	2.60	0.72
LAKE2	GI1	80	54	D-RCP	0.30%	0.56	0.80	2.75
GI1	JB2	240	54	□-RCP	0.10%	0.80	1.04	2.75
JB2	GI3	17	48	□-RCP	1.10%	1.04	1.24	3,48
GI3	GI4	55	48	U-RCP	0.09%	1.73	1.78	3.40
GI4	CI5	112	48	D-RCP	0.10%	1.78	1.89	2.82
CI5	JB6	131	48	D-RCP	0.08%	1.89	2.02	2.87
JB6	JB7	185	48	II-RCP	0.11%	2.02	2.20	2.61
JB7	JB13	44	48	O-RCP	0.11%	2.20	2.25	2,55
JB13	JB14	65	48	O-RCP	0.31%	2,25	2.45	2.60
JB13 JB14	JB28	246	48	U-RCP	0.31%	2.45	2.45 2.69	2.44
JB28	GI41	220	48	U-RCP	0.10%	2.45 2.69	2.87	2.25
GI41	JB42	118	48	U-RCP	0.05%	2.87	2.93	2.28
JB42	GI43	158	48	D-RCP	0.05%	2.93	3.01	2.13
GI43	GI44	145	42	D-RCP	0.11%	3.22	3.37	2.07
GI44	GI45	200	42	□-RCP	0.05%	3.37	3,47	1.83
GI45	GI46	198	42	D-RCP	0.05%	3.47	3.57	1.75
GI46	JB51	35	42	□-RCP	0.05%	3.57	3.60	1.66
JB51	GI52	231	42	□-RCP	0.05%	3.60	3.68	1.52
G152	JB53	58	42	O-RCP	0.05%	3.68	3.72	1.60
JB53	JB61A	323	36	D-RCP	0.05%	3.72	3.87	1.07
JB61A	GI61	61	30	□-RCP	0.05%	3.87	3.90	1.07
GI61	JB62	318	30	□-RCP	0.05%	3.90	4.08	0.57
45TH A\	/E							
JB14	GI16	42	24	□-RCP	0.20%	3.82	3.89	2.85
GI16	GI18	153	24	□-RCP	0.20%	3.89	4,22	2,30
GI18	GI19	26	18	□-RCP	0.19%	4.22	4,27	0.37
GI18	GI20	103	24	□-RCP	0.20%	4.22	4.43	2.21
GI20	GI21	25	18	□-RCP	0.16%	4.43	4.47	0.41
GI20	GI22	130	18	U-RCP	0.17%	4.47	4.67	2.30
G122	GI24 GI25	50	14x23	ELLIP. RCP	0.10%	4.69	4.75	0.82
GI25	GI25	41 31	14×23 14×23	ELLIP, RCP ELLIP, RCP	0.32%	4.67 4.75	4.75 4.85	0.80 1.41
GI26	GI27	23	14x23	ELLIP. RCP	0.32%	4.85	4.90	1.59
<u>urco</u>	UIL/		TTALO	CCCII I NOI	VILLE	4100	1170	1105
46TH A\	/E							
JB28	G132	107	24	□-RCP	0.25%	3.71	3.98	2.14
GI32	GI33	98	24	□-RCP	0.20%	3.98	4.18	2.38
GI33	GI34	35	18	□-RCP	0.21%	4.18	4.25	0.66
GI33	GI35	96	24	□-RCP	0.21%	4.18	4.38	2.13
GI35	GI36	35	18	O-RCP	0.20%	4,38	4.45	0.57
GI35	GI37	91	18	□-RCP	0.19%	4.38	4.56	2.03
GI37	GI38	26	14×23	ELLIP. RCP	0.23%	4.56	4.62	0.46
GI37	GI39	66	14×23	ELLIP, RCP	0.21%	4.56	4,70	1.20
GI39	GI40	55	14×23	ELLIP. RCP	0.23%	4.70	4.75	0.78
4000	,_							
49TH A\		400	<u> </u>		1.00**	0.44	4.00	4.4-
JB51 GI47	GI47	198	24	O-RCP	1.90%	3.60	4.03	1.66
GI47A	GI47A GI48	239 35	24 18	O-RCP	0.20% 0.17%	4.03 4.44	4.44 4.50	1.56 2.47
GI47A GI48	GI49	113	18 14×23	ELLIP, RCP	0.17%	4.50	4.69	2.18
GI49	GI50	31	14x23	ELLIP, RCP	0.17%	4.69	4.75	0.89
			_ ,,,					1 2
50TH AV	Æ							
JB53	GI54	227	24	□-RCP	0.18%	3.72	4.14	0.97
GI54	GI55	136	24	O-RCP	0.16%	4.14	4.36	1.68
GI55	GI56	23	15	□-RCP	0.30%	4.36	4,43	0.94
GI55	GI57	78	18	O-RCP	0.17%	4.36	4.49	0.94
GI57	GI58	25	14×23	ELLIP. RCP	0.16%	4.49	4.53	0.75
GI58	GI59	114	14×23	ELLIP, RCP	0.16%	4.53	4.71	1.44
GI59	GI60	23	14×23	ELLIP, RCP	0.17%	4.71	4.75	0.84
246	_							
51ST AV	1							
JB61	GI63	157	24	D-RCP	0.24%	3.90	4.24	1.49
GI63	GI65	290	18	U-RCP	0.18%	4.24	4.76	0.87
GI65	GI64	26	14x23	ELLIP, RCP	0.20%	4.87	4.81	0.87
GI64	GI66	54	14×23	ELLIP. RCP	0.18%	4.81	4.91	1.12
52ND A\	/F		<u> </u>					
JB62	GI68	200	24	□-RCP	0.10%	4.08	4.29	0.57
GI68	GI68A	182	18	D-RCP	0.10%	4.08	4.47	1.82
GI68A	GI69	25	14×23	ELLIP. RCP	0.20%	4.47	4.52	1.70
GI69 -	GI70	55	14×23	ELLIP. RCP	0.18%	4.52	4.57	0.75
GI69	GI71	67	14×23	ELLIP, RCP	0.13%	4.52	4.6	0.47
GI71	GI72	28	14×23	ELLIP. RCP	0.14%	4.61	4.65	0.39
						- 		


STRUCTURE CHART

NUMBER RIM IE

	NUMBER	RIM	IE	TYPE
	GI1	8.00	0.80	GRATE INLET
	JB2	8.75	1.04	JUNCTION BOX
	GI3	8.70	1,24	GRATE INLET
	GI4	8.50	1.78	GRATE INLET
	CI5	9.66	1.89	CURB INLET
	JB6	12.78	2.02	JUNCTION BOX
	JB7	12.16	2.20	JUNCTION BOX
	JB13	9.90	2,25	JUNCTION BOX
	JB14	8.90	2.45	JUNCTION BOX
	GI16	9.30	3.89	GRATE INLET
	GI18	8.10	4,22	GRATE INLET
	GI19	8.10	4.27	GRATE INLET
	GI20	8.00	4.43	GRATE INLET
	GI21	8.00	4.47	GRATE INLET
	G122	7.50	4.67	GRATE INLET
	JB23	7.30	4.72	JUNCTION BOX
۱	GI24	7.20	4.75	GRATE INLET
	GI25	7.50	4.75	GRATE INLET
	GI26	7.40	4.85	GRATE INLET
	GI27	7.40	4,90	GRATE INLET
	JB28	9.00	2.69	JUNCTION BOX
				· · · · · · · · · · · · · · · · · · ·
	JB29	8.50	2.78	JUNCTION BOX
	7B30	8.90	3.81	JUNCTION BOX
۱	JB31	8.90	3.87	JUNCTION BOX
	G132	8.30	3,98	GRATE INLET
- 1	GI33	7.75	4.18	GRATE INLET
	GI34	7.40	4.25	GRATE INLET
١	GI35	7.50	4.38	GRATE INLET
ŀ	GI36	7.50	4,45	GRATE INLET
1		7.10	4.56	GRATE INLET
	GI37			
-	GI38	7.10	4.62	GRATE INLET
١	GI39	7.10	4.70	GRATE INLET
	GI40	7.10	4.75	GRATE INLET
	GI41	8.63	2.87	GRATE INLET
	JB42	9.10	2,93	JUNCTION BOX
	GI43	8.80	3.01	GRATE INLET
١	GI44	8.80	3.37	GRATE INLET
-	GI45	9.25	3.47	GRATE INLET
	GI46	9.25	3.57	GRATE INLET
	GI47	8,50	4.03	JUNCTION BOX
	GI47A	7.50	4.44	JUNCTION BOX
	GI48	7.50	4.50	GRATE INLET
	GI49	7.10	4.69	GRATE INLET
	GI50	7.10	4.75	GRATE INLET
	JB51	9,27	3.60	JUNCTION BOX
	GI52	9,27	3.68	GRATE INLET
			· · · · · · · · · · · · · · · · · · ·	
	JB53	9.75	3.72	JUNCTION BOX
	GI54	8.40	4.14	GRATE INLET
	GI55	7.50	4.36	GRATE INLET
	GI56	7.50	4.43	GRATE INLET
	GI57	7.10	4.49	GRATE INLET
	GI58	7.10	4.53	GRATE INLET
	GI59	7.00	4.71	GRATE INLET
	GI60	7.00	4.75	GRATE INLET
	GI61	9.40	3.90	JUNCTION BOX
	JB61A	9.40	3.87	JUNCTION BOX
	JB62	9,90	4.08	JUNCTION BOX
	GI63	8.80	4.24	GRATE INLET
	GI64	7.25	4.81	GRATE INLET
١	GI65	7.25	4.76	GRATE INLET
	GI66	7.10	4.91	GRATE INLET
	GI68	8.90	4.29	GRATE INLET
	GI68A	8.00	4.47	GRATE INLET
	GI69	7.10	4.52	GRATE INLET
	GI70	7.10	4.57	GRATE INLET
۱	GI71	7.00	4.61	GRATE INLET
	G172	7.00	4.65	GRATE INLET
	JB73	10,50	2.62	JUNCTION BOX
	JB74	9.50	2.34	JUNCTION BOX
	JB75	8.50	2.15	JUNCTION BOX
	CS76	6.50	3.40	CONTROL STURUCTUR
	JB77	10.40	3.10	JUNCTION BOX
	JB78	6.50	2.86	JUNCTION BOX
	JB79	6.15	2,21	JUNCTION BOX
		6.50		
	JB80 JB81		2.04	
		7.25	1.97	JUNCTION BOX
ı	3801	7,23	2177	



LEGEND



GRAPHIC SCALE (IN FEET) 1 inch = 30 ft.

SEQUENCE OF EVENTS

REMOVE PAVEMENT

PROPOSED GRATE INLET/JUNCTION BOX

W/TYPE A INLET PROTECTION (SEE DETAIL)

I) PRECONSTRUCTION MEETING 2) INSTALL EROSION CONTROL & TREE PROTECTION 3) INSTALL STORM DRAINAGE LINES) LANDSCAPE/STABILIZE ALL DISTURBED AREAS AS LINEAR WORK IS COMPLETED

5) REMOVE EROSION CONTROLS ONCE 6) SUBMIT NOTICE OF TERMINATION (NOT)

1) THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE CSE, THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE **EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE** COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTORS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.

2) CONTRACTOR SHALL BE REQUIRED TO HAVE PROPOSED **ROUTE STAKED, ALL UTILITIES MARKED, UTILITY CROSSINGS** VERTICALLY LOCATED, AND A WALK THROUGH CONDUCTED WITH ENGINEER PRIOR TO INITIATION OF CONSTRUCTION OF ANY PORTION OF THE WORK.

3) SEE SHEET C200 FOR PIPE AND STRUCTURE CHART AND

4) CONTRACTOR TO COORDINATE ALL ACTIVITIES INVOLVING DISTURBANCE OF GOLF COURSE AREAS WITH WILD DUNES RESORT GOLF COURSE SUPERVISOR. FINAL REESTABLISHMENT OF DISTURBED AREAS TO BE PERFORMED BY CONTRACTOR FROM APPROVED LIST OF GOLF COURSE RESTORATION

5) PER USACOE LETTER OF JANUARY 28, 2013 (SAC 2012-01136-2JY) DEPARTMENT OF THE ARMY AUTHORIZATION WILL NOT BE REQUIRED FOR MECHANIZED LAND CLEARING, EXCAVATION, OR THE PLACEMENT OF DREDGED OR FILL MATERIAL ON THIS SITE

6) ANY FIELD CHANGES THAT WOULD IMPACT SCDOT R/W WILL REQUIRE WRITTEN SCDOT APPROVAL PRIOR TO CHANGES BEING IMPLEMENTED IN THE FIELD.

7) WORK WITHIN SCDOT RIGHT-OF-WAYS SHALL COMPLY WITH **CURRENT SCDOT STANDARD DRAWINGS AND SPECIFICATIONS.** WORK IN OTHER AREAS SHALL COMPLY WITH SCDOT STANDARDS UNLESS OTHERWISE NOTED.

GENERAL PROJECT NOTES

WATER VALVE

IRRIGATION SPRINKLER

REPLACEMENT AREA

- 1. SURVEYING INFORMATION SUPPLIED BY OTHERS. THIS INFORMATION HAS NOT BEEN INDEPENDENTLY VERIFIED BY CSE.
- 2. ALL ELEVATIONS REFER TO NGVD 29 DATUM.

3. THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY CSE, THE OWNER OR ITS REPRESENTATIVE. EFFORTS HAVE BEEN MADE TO SHOW LOCATIONS OF UNDERGROUND UTILITIES ON THESE PLANS, HOWER THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTORS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.


- 4. THE CONTRACTOR WILL NOTIFY THE ENGINEER IF UNSUITABLE MATERIAL IS DISCOVERED PRIOR TO BEGINNING ANY REMOVAL.
- 5. ALL PAVING, GRADING AND DRAINAGE MATERIALS SHALL BE IN ACCORDANCE WITH SCDOT CURRENT STANDARDS. ALL WORK PERTAINING TO WATER AND SEWER FACILITIES SHALL BE IN ACCORDANCE WITH ISLE OF PALMS WATER AND SEWER COMMISSION CURRENT STANDARDS AND SPECIFICATIONS.
- 6. NO CONSTRUCTION SHALL TAKE PLACE WITHIN WETLANDS UNLESS A PERMIT HAS BEEN PREVIOUSLY OBTAINED.
- 7. ALL STORM PIPE SHALL BE REINFORCED CONCRETE PIPE (RCP) CONFORMING TO ASTM C-76 CLASS III. JOINTS SHALL BE WATER TIGHT FLEXIBLE RUBBER GASKET AND SHALL MEET ASTM C-443 AND AASHTO M-198. PIPE JOINTS SHALL BE WRAPPED WITH NON-WOVEN GEOTEXTILE FABRIC.
- 8. RIP-RAP WILL BE PLACED AS INDICATED ON PLANS IMMEDIATELY AFTER INSTALLATION OF STORM PIPE TO REDUCE SEDIMENTATION AND EROSION DOWNSTREAM.
- 9. CONTRACTOR IS TO INSTALL SILT FENCE ALONG WETLANDS, WHERE INDICATED ON THE PLANS, SPECIFIED BY THE ENGINEER AND WHERE DISTURBED AREAS MAY CAUSE SILTATION OF THE WETLAND AND/OR ADJACENT PROPERTY. SILT FENCE SHALL BE INSTALLED AROUND ALL DRAINAGE INLETS (CURB INLETS, GRATE INLETS, ETC.) DURING CONSTRUCTION UNTIL FINAL STABILIZATION IS OBTAINED AROUND STRUCTURE (ASPHALT OR GRASS). SEE DETAIL.
- 10. THIS PROJECT IS SITUATED IN FLOOD ZONE VE(16), AE(16), AE(15), AE(14) FROM COMMUNITY PANEL #45019C 0561J EFFECTIVE DATE NOVEMBER 17, 2004.
- 11. OVERLAY AREAS FOR INTERSECTIONS WILL CONTINUE TO TANGENT POINTS ON INTERSECTION RADII UNLESS OTHERWISE NOTED. OVERLAY SHALL MEET CURRENT SCDOT STANDARDS.
- 12. TRIMMING/LIMBING OF TREES MAY BE REQUIRED. REMOVAL OF TREES GREATER THAN 7"DBH WILL REQUIRE PERMIT. CONTRACTOR TO CONTACT ENGINEER IF TREE REMOVALS NOT INDICATED ON PLANS WILL BE NECESSARY. CONTRACTOR SHALL ENGAGE A QUALIFIED ARBORIST TO PERFORM ANY NECESSARY TRIMMING, LIMBING, OR RELOCATION OF EXISTING TREES. IF ROOTS ARE ENCOUNTERED DURING CONSTRUCTION THEY SHALL BE CLEANLY CUT TO THE MINIMUM EXTENT NECESSARY POSSIBLE AND ADDITIONAL TREATMENT AS RECOMMENDED BY ARBORIST SHALL BE
- 13. CONTRACTOR SHALL COORDINATE ALL WATER AND GRAVITY SEWER LINE CROSSINGS WITH IOPWSC. WATER AND SEWER SERVICE LINE LOCATIONS ARE APPROXIMATE; CONTRACTOR SHALL FIELD VERIFY DURING EXCAVATION. WHERE NEW DRAINAGE PIPE CROSSES EXISTING WATER SERVICES, CONTRACTOR SHALL FIELD ADJUST SERVICE LINE AS REQUIRED PER IOPWSC SPECIFICATIONS. IN COORDINATION WITH IOPWSC, CONTRACTOR SHALL RELOCATE ANY WATER METER WHERE EXISTING LOCATIONS CONFLICT WITH PROPOSED IMPROVEMENTS. EXISTING SEWER SERVICE LATERALS OR CLEANOUT CONFLICTS SHALL BE ADJUSTED BY CONTRACTOR AS PER SEWER SERVICE CONFLICT DETAIL. CONTRACTOR SHALL DETERMINE CONFLICTS AND MAKE ADJUSTMENTS AS PRACTICAL PRIOR TO START OF DRAINAGE INSTALLATION.
- 14. EXISTING PAVEMENTS SHALL BE SAWCUT AS NECESSARY FOR DRAINAGE PIPE INSTALLATION. CONTRACTOR SHALL MILL & OVERLAY ROADWAYS AND REPAIR CART PATHS AS SHOWN ON THE PLANS AND DETAILS AND PER SCDOT SPECIFICATIONS. CONTRACTOR SHALL REPAIR AND RESTORE DRIVEWAYS WITH SAME MATERIALS OR APPROVED ALTERNATIVE AS PER MANUFACTURER'S RECOMMENDATIONS AND SCOOT REQUIREMENTS. ALTERNATIVES MUST BE APPROVED BY ENGINEER PRIOR TO INSTALLATION. PAVING RESTORATION LIMITS SHOWN ON PLANS ARE APPROXIMATE AND CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIR OR REPLACEMENT OF ANY PAVEMENT, CURBING, SIDEWALKS OR CART PATHS DAMAGED DURING WORK ASSOCIATED WITH THIS PROJECT.
- 15. PIPE BACKFILL SHALL BE FREE OF ORGANIC MATERIALS AND BE COMPACTED TO 95% MODIFIED PROCTOR. CONTRACTOR SHALL PROVIDE APPROPRIATE COMPACTION TESTING IN ACCORDANCE
- 16. FOR ANY NECESSARY DEWATERING, CONTRACTOR SHALL PROVIDE TREATMENT TO REMOVE SEDIMENT PRIOR TO DISCHARGE OF WATER FROM TRENCHES. DISCHARGES FROM PUMPS USED FOR ANY SITE DEWATERING SHALL BE ROUTED THROUGH ONSITE BMPS FOR TREATMENT PRIOR TO DISCHARGE TO ANY WETLAND, WATERWAY OR OTHER SURFACE WATER/CONVEYANCE. IF FILTER BAGS ARE TO BE USED ON PUMP DISCHARGE PIPES THE BAGS SHALL BE APPROPRIATELY SIZED FOR PUMP DISCHARGE RATE (PER MANUFATURER GUIDELINES) AND SHALL BE SECURED TO END OF OUTLET PIPE PER MANUFACTURER SPECIFICATIONS. BAGS SHALL BE PLACED ON IMPERVIOUS LINER AND IN LOCATIONS WHERE THEY WILL NOT BE DISTURBED BY CONSTRUCTION OR OTHER TRAFFIC, SHALL BE POSITIONED SO AS NOT TO CREATE THE POTENTIAL FOR ADDITIONAL EROSION, AND SHALL BE PLACED SUCH THAT DISCHARGE FROM THE BAGS WILL RUN ACROSS UNDISTURBED BUFFER AREAS PRIOR TO IT REACHING ANY WATERWAY OR WETLAND. FILTER BAGS SHALL BE CHECKED DAILY DURING THEIR USE TO MAKE SURE SEDIMENT CAPACITY HAS NOT BEEN EXCEEDED (PER MANUFACTURER SPECIFICATIONS) AND REPLACED AS NECESSARY. BAGS SHALL BE DISPOSED OF PROPERLY AND TRAPPED SEDIMENT WITHIN THE BAG REMOVED FROM SITE OR, IF PLACED BACK ON SITE, SHALL BE SPREAD IN APPROPRIATELY PROTECTED AREAS AND STABILIZED PER OS-SWPPP REQUIREMENTS.
- 17. CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS WHEN OPEN TRENCHING TO PRESERVE PUBLIC SAFETY.
- 18. CONTRACTOR SHALL BE RESPONSIBLE FOR REPLACEMENT, RESTORATION OR REPAIR OF ANY SIDEWALKS, MAILBOXES, ENCLOSURES, FENCES, LANDSCAPING, BOLLARDS OR ANY OTHER EXISTING APPURTENANCES THAT ARE DAMAGED OR REMOVED FOR INSTALLATION OF DRAINAGE SYSTEM. THESE ITEMS SHALL BE RESTORED TO EXISTING LOCATION AND GRADE UNLESS OTHERWISE NOTED. PRIOR TO CONSTRUCTION CONTRACTOR SHALL BE RESPONSIBLE FOR DOCUMENTING & CATALOGING EXISTING FACILITIES FOR USE IN POST CONSTRUCTION RESTORATION PROCESS.
- 19. CONTRACTOR SHALL BE RESPONSIBLE FOR TRAFFIC CONTROL MEASURES AND SHALL COMPLY WITH ALL SCOOT STANDARDS. IF ANY ROAD CLOSURES BECOME NECESSARY DURING CONSTRUCTION, THE TIMING AND DURATION OF THE CLOSURE WILL COMPLY WITH SCOOT PERMIT CONDITIONS AND BE COORDINATED WITH SCOOT AND CITY OF ISLE OF PALMS PRIOR TO CONSTRUCTION. CONTRACTOR WILL BE RESPONSIBLE FOR SUPPLYING NECESSARY TRAFFIC CONTROL PLAN PRIOR TO LANE CLOSURE AND SHALL SUPPLY ALL PERSONNEL AND MATERIALS NECESSARY FOR LANE CLOSURES.
- 20. HOURS OF WORK SHALL COMPLY WITH SCOOT PERMIT CONDITIONS (IF ANY), ANY AND ALL REGULATIONS AND ORDINANCES OF THE CITY OF ISLE OF PALMS, AND THOSE HOURS STIPULATED WITHIN PROJECT SPECIFICATIONS. IN THE EVENT OF A CONFLICT THE MORE RESTRICTIVE WORK HOURS SHALL GOVERN. ANY AND ALL APPLICABLE NOISE ORDINANCES SHALL BE ADHERED TO.
- 21. DRAINAGE STRUCTURE ELEVATIONS SHOW ON PLAN REPRESENT RIM ELEVATIONS UNLESS OTHERWISE NOTED. CONTRACTOR SHALL BE RESPONSIBLE FOR ADJUSTING RIM ELEVATIONS TO FINISHED GRADE AT NO ADDITIONAL COST. IF PREFABRICATED BOXES ARE USED THEY SHOULD BE CONSTRUCTED 6" SHORTER THAN NECESSARY AND BROUGHT TO FINISHED GRADE WITH LEVELING BRICKS. CONTRACTOR SHALL GRADE AREA IMMEDIATELY ADJACENT TO GRATE INLETS TO PROVIDE POSITIVE DRAINAGE TO INLET UNLESS OTHERWISE NOTED ON PLANS.
- 22. CONTRACTOR SHALL NOTIFY ENGINEER AND OWNER 48 HRS PRIOR TO REQUIRED TESTING & INSPECTION. CONTRACTOR SHALL PROVIDE NOTIFICATIONS TO SCDOT PER STIPULATIONS OF ENCROACHMENT PERMITS OR AS REQUIRED BY CURRENT SCDOT STANDARDS AND SPECIFICATIONS.
- 23. ROADWAYS SHALL BE CLEANED DAILY. CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER DISPOSAL OF ANY EXCAVATIONS, CONSTRUCTION DEBRIS OR OTHER MATERIALS. IN NO CASE ARE PRIVATE LOTS TO BE USED FOR STOCKPILING OF MATERIALS OR CONSTRUCTION DEBRIS.
- 24. ANY FIELD CHANGES WITHIN SCDOT R/W OR CHANGES THAT WOULD IMPACT SCDOT R/W (E.G. DRAINAGE, GRADING, ACCESS DESIGN ETC.) WILL REQUIRE WRITTEN SCDOT APPROVAL PRIOR TO CHANGES BEING IMPLEMENTED IN THE FIELD.
- 25. LIMITS OF PAVING MILL/OVERLAY RESTORATIONS AND REPLACEMENTS ARE APPROXIMATE. AREAS OF PAVEMENT REMOVED OR DAMAGED, BEYOND AREAS SHOWN ON PLANS, SHALL BE
- 26. CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVAL AND DISPOSAL OF ANY EXCESS MATERIAL GENERATED FROM EXCAVATIONS FOR ANY PART OF THE WORK ASSOCIATED WITH THE PROJECT. EXCAVATED MATERIAL IS TO BE REMOVED PROMPTLY AND SHALL NOT BE STORED ONSITE.

REV REV REV REV **50846**

DRAWN BY: JCM FILE: 920-PH2-C200

SCALE: NONE

DATE: 6-28-13








668 MARINA DRIVE SUITE B-1 CHARLESTON, S.C. 29492


PHONE: (843) 849-8945 FAX: (843) 849-8974 CSE@CIVILSITEENV.COM


CSE JOB NUMBER





































REVISIONS:
1) REV 8/23/13 PER LOWE WILD DUNES,
2) REV 7/16/14 PER SCDOT COMMENTS
3) REV 5/31/17 CONSTRUCTION BID SET **PROFILES** ROJECT: 45TH DRAWN BY: JCM FILE: 920-PH2-C300

SCALE: AS NOTED DATE: 6-28-13










668 MARINA DRIVE SUITE B-1 CHARLESTON, S.C. 29492

PHONE: (843) 849-8945 FAX: (843) 849-8974 EMAIL: CSE@CIVILSITEENV.COM

CSE JOB NUMBER 920-PH2







SILT FENCE DETAIL **MATERIALS**

USE 48-INCH LONG STEEL POSTS THAT MEET THE FOLLOWING MINIMUM PHYSICAL REQUIREMENTS: COMPOSED OF HIGH STRENGTH STEEL WITH MINIMUM YIELD STRENGTH OF 50,000 PSI.

HAVE A STANDARD "T" SECTION WITH A NOMINAL FACE WIDTH OF 1.38-INCHES AND NOMINAL "T" LENGTH OF 1.48-INCHES. WEIGH 1.25 POUNDS PER FOOT (±8%).

HAVE A SOIL STABILIZATION PLATE WITH A MINIMUM CROSS SECTION AREA OF 17-SQUARE INCHES ATTACHED TO THE STEEL POSTS. PAINTED WITH A WATER BASED BAKED ENAMEL PAINT.

USE STEEL POSTS WITH A MINIMUM LENGTH OF 4-FEET, WEIGHING 1.25 POUNDS PER LINEAR FOOT (\pm 8 AID IN FASTENING THE FABRIC. EXCEPT WHEN HEAVY CLAY SOILS ARE PRESENT ON SITE, STEEL POSTS WILL HAVE A METAL SOIL STABILIZATION PLATE WELDED NEAR THE BOTTOM SUCH THAT WHEN THE POST IS DRIVEN TO THE PROPER DEPTH, THE PLATE WILL BE BELOW THE GROUND LEVEL FOR ADDED STABILITY.

THE SOIL PLATES SHOULD HAVE THE FOLLOWING CHARACTERISTICS: BE COMPOSED OF MINIMUM 15 GAUGE STEEL. HAVE A MINIMUM CROSS SECTION AREA OF 17-SQUARE INCHES.


GEOTEXTILE FILTER FABRIC

COMPOSED OF FIBERS CONSISTING OF LONG CHAIN SYNTHETIC POLYMERS COMPOSED OF AT LEAST 85 POLYOLEFINS, POLYESTERS, OR POLYAMIDES. FORMED INTO A NETWORK SUCH THAT THE FILAMENTS OR YARNS RETAIN DIMENSIONAL STABILITY RELATIVE TO EACH OTHER. FREE OF ANY TREATMENT OR COATING WHICH MIGHT ADVERSELY ALTER ITS PHYSICAL PROPERTIES AFTER INSTALLATION. FREE OF DEFECTS OR FLAWS THAT SIGNIFICANTLY AFFECT ITS PHYSICAL AND/OR FILTERING PROPERTIES. CUT TO A MINIMUM WIDTH OF 36 INCHES.

USE ONLY FABRIC APPEARING ON SCDOT APPROVAL SHEET #34 MEETING THE REQUIREMENTS OF THE MOST CURRENT EDITION OF THE SCDOT STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.


EXCAVATE A TRENCH APPROXIMATELY 6-INCHES WIDE AND 6-INCHES DEEP WHEN PLACING FABRIC BY HAND. PLACE 12-INCHES OF GEOTEXTILE FABRIC INTO THE 6-INCH DEEP TRENCH, EXTENDING THE REMAINING 6-INCHES TOWARDS THE UPSLOPE SIDE OF THE TRENCH. BACKFILL THE TRENCH WITH SOIL OR GRAVEL AND COMPACT.BURY 12-INCHES OF FABRIC INTO THE GROUND WHEN PNEUMATICALLY INSTALLING SILT FENCE WITH A SLICING METHOD. PURCHASE FABRIC IN CONTINUOUS ROLLS AND CUT TO THE LENGTH OF THE BARRIER TO AVOID JOINTS. WHEN JOINTS ARE NECESSARY, WRAPPED THE FABRIC TOGETHER AT A SUPPORT POST WITH BOTH ENDS FASTENED TO THE POST, WITH A 6-INCH MINIMUM OVERLAP, INSTALL POSTS TO A MINIMUM DEPTH OF 24-INCHES. INSTALL POSTS A MINIMUM OF 1- TO 2- INCHES ABOVE THE FABRIC, WITH NO MORE THAN 3-FEET OF THE POST, ABOVE THE GROUND. SPACE POSTS TO MAXIMUM 6-FEET CENTERS. ATTACH FABRIC TO WOOD POSTS USING STAPLES MADE OF HEAVY-DUTY WRE AT LEAST 1½-INCH LONG, SPACED A MAXIMUM OF 6-INCHES APART. STAPLE A 2-INCH WIDE LATHE OVER THE FILTER FABRIC TO SECURELY FASTEN IT TO THE UPSLOPE SIDE OF WOODEN POSTS. ATTACH FABRIC TO THE STEEL POSTS USING HEAVY-DUTY PLASTIC TIES THAT ARE EVENLY SPACED AND PLACED IN A MANNER TO PREVENT SAGGING OR TEARING OF THE FABRIC. IN CALL CASES, TIES SHOULD BE AFFIXED IN NO LESS THAN 4 PLACES. INSTALL THE FABRIC A MINIMUM OF 24-INCHES ABOVE THE GROUND. WHEN NECESSARY, THE HEIGHT OF THE FENCE ABOVE GROUND MAY BE GREATER THAN 24-INCHES. IN TIDAL AREAS, EXTRA SILT FENCE HEIGHT MAY BE REQUIRED. THE POST HEIGHT WILL BE TWICE THE EXPOSED POST HEIGHT. POST SPACING WILLREMAIN THE SAME AND EXTRA HEIGHT FABRIC WILL BE 4-, 5-, OR 6-FEET TALL. LOCATE SILT FENCE CHECKS EVERY 100 FEET MAXIMUM AND AT LOW POINTS. INSTALL THE FENCE PERPENDICULAR TO THE DIRECTION OF FLOW AND PLACE THE FENCE THE PROPER DISTANCE FROM THE TOE OF STEEP SLOPES TO PROVIDE SEDIMENT STORAGE AND ACCESS FOR MAINTENANCE AND

INSPECT EVERY SEVEN CALENDAR DAYS AND WITHIN 24-HOURS AFTER EACH RAINFALL EVENT THAT PRODUCES 1/2-INCHES OR MORE OF PRECIPITATION. CHECK FOR SEDIMENT BUILDUP AND FENCE INTEGRITY. CHECK WHERE RUNOFF HAS ERODED A CHANNEL BENEATH THE FENCE, OR WHERE THE FENCE HAS SAGGED OR COLLAPSED BY FENCE OVERTOPPING. IF THE FENCE FABRIC TEARS, BEGINS TO DECOMPOSE, OR IN ANY WAY BECOMES INEFFECTIVE, REPLACE THE SECTION OF FENCE IMMEDIATELY. REMOVE SEDIMENT ACCUMULATED ALONG THE FENCE WHEN IT REACHES 1/3 THE HEIGHT OF THE FENCE, ESPECIALLY IF HEAVY RAINS ARE EXPECTED. REMOVE TRAPPED SEDIMENT FROM THE SITE OR STABILIZE IT ON SITE. REMOVE SILT FENCE WITHIN 30 DAYS AFTER FINAL STABILIZATION IS ACHIEVED OR AFTER TEMPORARY BEST MANAGEMENT PRACTICES (BMPS) ARE NO LONGER NEEDED. PERMANENTLY STABILIZE DISTURBED AREAS RESULTING FROM FENCE REMOVAL




FOR 8" CURB FACE HEIGHT AT LANDSCAPE ISLAND PROVIDE 1/4" BEVEL TYP. DOWN SLOPE SECTION -SLOPED TOWARD GUTTER -1" BATTER -(18**"**) 24**"**-


> ALTERNATE DOWN SLOPE SECTION TO BE USED ONLY WHEN DRAINING AWAY FROM CURB. 18" & 24" CURB & GUTTER DETAIL



ROLL CURB & GUTTER DETAIL



CONCRETE SIDEWALK DETAIL



FILTER FABRIC

FILTER FABRIC BURIAL DETAIL

TYPE A - FILTER FABIC INLET PROTECTION N.T.S

FILTER FABRIC INLET PROTECTION

USE FILTER FABRIC THAT CONFORMS TO SCDOT STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION (LATEST EDITION). REFER TO THE SILT FENCE GEOTEXTILE FABRICS APPROVAL SHEET #34.

USE STEEL POSTS THAT MEET THE FOLLOWING MINIMUM PHYSICAL REQUIREMENTS: BE COMPOSED OF HIGH STRENGTH STEEL WITH MINIMUM YIELD STRENGTH OF 50,000 PSI. HAVE A STANDARD "T" SECTION WITH A NOMINAL FACE WIDTH OF 1.38-INCHES AND NOMINAL "T" LENGTH OF 1.48-INCHES. WEIGH 1.25 POUNDS PER BOOSTS) BE PAINTED WITH A WATER BASED BAKED ENAMEL PAINT.

ATTACH FABRIC TO METAL POSTS WITH HEAVY-DUTY PLASTIC TIES.

EXCAVATE A TRENCH 6-INCHES WIDE AND 6-INCHES DEEP AROUND THE OUTSIDE PERIMETER OF THE INLET UNLESS THE FABRIC IS PNEUMATICALLY INSTALLED.

EXTEND THE FILTER FABRIC A MINIMUM OF 12-INCHES INTO THE TRENCH. BACKFILL THE TRENCH WITH SOIL OR CRUSHED STONE AND COMPACT OVER THE FILTER FABRIC UNLESS THE FABRIC IS

USE STEEL POSTS WITH A MINIMUM POST LENGTH OF 60-INCHES CONSISTING OF STANDARD "T" SECTIONS WITH A WEIGHT OF 1.25 POUNDS PER FOR \$20. INSTALL THE FILTER FABRIC TO A MINIMUM HEIGHT OF 24-INCHES ABOVE GRADE. SPACE THE STEEL POSTS AROUND THE PERIMETER OF THE INLET A MAXIMUM OF 3-FEET APART AND DRIVE THEM INTO THE GROUND A MINIMUM OF 24-INCHES. CUT THE FILTER FABRIC FROM A CONTINUOUS ROLL TO THE LENGTH OF THE PROTECTED AREA TO AVOID THE USE OF JOINTS. WHEN JOINTS ARE NECESSARY, WRAP FILTER FABRIC TOGETHER ONLY AT A SUPPORT POST WITH BOTH ENDS SECURELY FASTENED TO

ATTACH FABRIC TO STEEL POSTS WITH HEAVY-DUTY PLASTIC TIES.

THE POST, WITH A MINIMUM 6-INCH OVERLAP.


ATTACH AT LEAST FOUR (4) EVENLY SPACED TIES IN A MANNER TO PREVENT SAGGING OR TEARING OF THE FABRIC. IN ALL CASES, AFFIX TIES IN NO LESS THAN FOUR (4) PLACES.

INSPECTIONS SHOULD BE MADE EVERY 7 CALENDAR DAYS AND WITHIN 24-HOURS AFTER EACH STORM THAT PRODUCES%-INCHES OR MORE OF RAIN. IF THE FABRIC BECOMES CLOGGED, IT SHOULD BE REPLACED. SEDIMENT SHOULD BE REMOVED WHEN IT REACHES APPROXIMATELY 1/3 THE HEIGHT OF THE FENCE. TAKE CARE NOT TO DAMAGE OR UNDERCUT FABRIC WHEN REMOVING SEDIMENT.IF A SUMP IS USED, SEDIMENT SHOULD BE REMOVED WHEN IT FILLS APPROXIMATELY 1/3 THE DEPTH OF THE HOLE.MAINTAIN THE POOL AREA, ALWAYS PROVIDING ADEQUATE SEDIMENT STORAGE VOLUME FOR THE NEXT STORM.


STORM DRAIN INLET PROTECTION STRUCTURES SHOULD BE REMOVED ONLY AFTER THE DISTURBED AREAS ARE PERMANENTLY STABILIZED. REMOVE ALL CONSTRUCTION MATERIAL AND SEDIMENT, AND DISPOSE OF THEM PROPERLY.


GRADE THE DISTURBED AREA TO THE ELEVATION OF THE DISPOSE OF THEM PROPERLY.

GRADE THE DISTURBED AREA TO THE ELEVATION OF THE DROP INLET STRUCTURE CREST. USE APPROPRIATE PERMANENT STABILIZATION METHODS TO STABILIZE BARE AREAS AROUND THE INLET.




TYPICAL PAVEMENT CUT & OVERLAY DETAIL





POST INSTALLATION DETAIL

SEDIMENT TUBE INSTALLATION DETAIL



SEDIMENT TUBE BURIAL DETAIL

TYPE A - SEDIMENT TUBE INLET PROTECTION

SEDIMENT TUBES FOR TYPE A INLET STRUCTURE FILTERS EXHIBIT THE FOLLOWING PROPERTIES: PRODUCED BY A MANUFACTURER EXPERIENCED IN SEDIMENT TUBE MANUFACTURING. COMPOSED OF COMPACTED GEOTEXTILES, CURLED EXCELSIOR WOOD, NATURAL COCONUT FIBERS, HARDWOOD MULCH OR A MIX OF THESE MATERIALS ENCLOSED BY A FLEXIBLE NETTING MATERIAL. STRAW, STRAW FIBER, STRAW BALES, PINE NEEDLES, AND LEAF MULCH ARE NOT ALLOWED UNDER THIS SPECIFICATION. UTILIZES OUTER NETTING THAT CONSISTS OF SEAMLESS, HIGH-DENSITY POLYETHYLENE PHOTODEGRADABLE MATERIALS TREATED WITH ULTRAVIOLET STABILIZERS OR A SEAMLESS, HIGH-DENSITY POLYETHYLENE NON-DEGRADABLE MATERIALS. DIAMETER

CURLED EXCELSIOR WOOD, OR NATURAL COCONUT ROLLED EROSION CONTROL PRODUCTS (RECPS) THAT ARE ROLLED UP TO CREATE A SEDIMENT TUBE ARE NOT ALLOWED UNDER THIS SPECIFICATION. SELECT APPLICABLE SEDIMENT TUBES FROM THE SCDOT APPROVED PRODUCTS LIST.


USE 48-INCH LONG WOOD POSTS THAT MEET THE FOLLOWING REQUIREMENTS. 2-INCH BY 2-INCH SIZE.

HEAVY-DUTY WIRE STAPLES AT LEAST 11/2-INCH LONG, SPACED A MAXIMUM OF 6-INCHES APART TO ATTACH THE FILTER FABRIC TO WOODEN STAKES.

USE 48-INCH LONG STEEL POSTS THAT MEET THE FOLLOWING MINIMUM PHYSICAL REQUIREMENTS: BE COMPOSED OF HIGH STRENGTH STEEL WITH MINIMUM YIELD STRENGTH OF 50,000 PSI. HAVE A STANDARD "T" SECTION WITH A NOMINAL FACE WIDTH OF 1.38-INCHES AND NOMINAL "T" LENGTH OF 1.48-INCHES. %). WEIGH 1.25 POUNDS PER FOOT (± 8 BE PAINTED WITH A WATER BASED BAKED ENAMEL PAINT.

REMOVE ALL ROCKS, CLODS, VEGETATION OR OTHER OBSTRUCTIONS SO INSTALLED SEDIMENT TUBES HAVE DIRECT CONTACT WITH THE UNDERLYING SOIL OR SURFACE. INSTALL SEDIMENT TUBES BY LAYING THEM CONSTRUCT A SMALL TRENCH TO A DEPTH THAT IS 20 % OF THE DIAMETER. LAY THE SEDIMENT TUBE IN THE TRENCH AND COMPACT THE UPSTREAM SEDIMENT TUBE SOIL INTERFACE. DO NOT COMPLETELY BURY SEDIMENT TUBES DURING INSTALLATION. LAP THE ENDS OF ADJACENT SEDIMENT TUBES A MINIMUM OF 6-INCHES TO PREVENT FLOW AND SEDIMENT FROM PASSING THROUGH THE FIELD JOINT. NEVER STACK SEDIMENT TUBES ON TOP OF ONE ANOTHER.INSTALL SEDIMENT TUBES USING WOODEN STAKES (2-INCH X 2-INCH) OR STEEL POSTS (STANDARD "U" OR "T" SECTIONS WITH A MINIMUM WEIGHT OF 1.25 POUNDS PER FOOT) A MINIMUM OF 48-INCHES IN LENGTH PLACED ON 2-FOOT CENTERS. INTERTWINE THE STAKES WITH THE OUTER MESH ON THE DOWNSTREAM SIDE, AND DRIVE THE STAKES IN THE GROUND TO A MINIMUM DEPTH OF 24-INCESTLEAVING LESS THAN 12-INCHES OF STAKE ABOVE THE EXPOSED SEDIMENT TUBE.

INSPECTION AND MAINTENANCE: INSPECT EVERY SEVEN CALENDAR DAYS AND WITHIN 24-HOURS AFTER EACH RAINFALL EVENT THAT PRODUCES 1/2-INCHES OR MORE OF PRECIPITATION. INSPECT SEDIMENT TUBES AFTER INSTALLATION FOR GAPS UNDER THE TUBES AND FOR GAPS BETWEEN JOINTS OF ADJACENT ENDS OF SEDIMENT TUBES. REPAIR RILLS, GULLIES, AND ALL UNDERCUTTING NEAR SEDIMENT TUBES. REMOVE AND/OR REPLACE INSTALLED SEDIMENT TUBES AS REQUIRED TO ADAPT TO CHANGING CONSTRUCTION SITE CONDITIONS. REMOVE ALL SEDIMENT TUBES FROM THE SITE WHEN THE FUNCTIONAL LONGEVITY IS EXCEEDED AS DETERMINED BY THE ENGINEER, INSPECTOR OR MANUFACTURER'S REPRESENTATIVE. DISPOSE OF SEDIMENT TUBES IN REGULAR MEANS AS NON-HAZARDOUS, INERT MATERIAL.



TREE PROTECTION BARRICADE DETAIL(CHAIN LINK FENCING)

ALL TREE PROTECTION BARRICADES MUST HAVE:

A. A TOP HORIZONTAL RAIL WITH THE CHAIN LINKED FENCING WIRED TO THE POST AND TOP RAIL. 2. TREE BARRICADES SHALL BE ERECTED AT A MINIMUM DISTANCE FROM THE BASE OF A PROTECTED TREE AND/OR GRAND TREE AS SHOWN ON PLANS OR AS ACCORDING TO THE FOLLOWING STANDARDS;

A. FOR PROTECTED TREES TWENTY-THREE INCHES (23") D.B.H. OR LESS, BARRICADES SHALL BE PLACED A MINIMUM DISTANCE OF TEN FEET (10') FROM THE BASE OF THE PROTECTED

B. FOR PROTECTED TREES GREATER THAN TWENTY-THREE INCHES (23") D.B.H. AND GRAND TREES, BARRICADES SHALL PROVIDE A DIAMETER OF PROTECTION AROUND THE TREE EQUAL IN FEET TO THE DIAMETER BREAST HEIGHT OF THE TREE (I.E., A 24" DIAMETER TREE REQUIRES A 24-FOOT DIAMETER PROTECTIVE BARRICADE.


TREE NOTE A CERTIFIED ARBORIST SHALL PRUNE AND TREAT ALL GRAND TREES ACCORDING TO THEIR EXPERTISE TO FURTHER PRESERVE THEM.


53

C

DRAWN BY: JCM FILE: 920-PH2-C400

SCALE: NONE DATE: 6-28-13









668 MARINA DRIVE SUITE B-1 CHARLESTON, S.C. 29492

PHONE: (843) 849-8945 FAX: (843) 849-8974 EMAIL: CSE@CIVILSITEENV.COM

CSE JOB NUMBER


920-PH2 SHEET NUMBER







SLAB TYPE INLET/BOX INSTALLTION ALTERNATIVE

NOTE: WORK WITHIN SCOOT RIGHT-OF-WAYS SHALL COMPLY WITH CURRENT SCOOT STANDARD DRAWINGS AND SPECIFICATIONS.





SECTION "A-A"



NOTE:


1) RIM ELEVATIONS ON PLANS ARE APPROXIMATE AND MAY REQUIRE FIELD ADJUSTMENT. IF PRECAST CONCRETE BOXES ARE USED, BOX HEIGHT SHALL BE 6" LOWER WITH FINAL RIM ELEVATION ACHIEVED THROUGH THE USE OF LEVELING BRICKS AND MORTAR.


2) REINFORCEMENT, CONSTRUCTION & MATERIALS TO COMPLY WITH SCDOT

STANDARD DRAWINGS 719-305-00, 719-505-02 THRU 719-505-04

JUNCTION BOX DETAIL
N.T.S.

AND 719-550-00






PLAN

RIM ELEVATIONS ON PLANS ARE APPROXIMATE AND MAY REQUIRE FIELD ADJUSTMENT. IF PRECAST CONCRETE BOXES ARE USED, BOX HEIGHT SHALL BE 6" LOWER WITH FINAL RIM ELEVATION ACHIEVED THROUGH THE USE OF LEVELING BRICKS AND MORTAR.
 REINFORCEMENT, CONSTRUCTION & MATERIALS TO COMPLY WITH SCDOT STANDARD DRAWINGS 719-110-01 & 719-305-00


TYPICAL GRATE INLET WITH SUMP DETAIL N.T.S.



SECTION "A-A"

CURB INLET THROAT DIMENSIONS AND REINFORCEMENT SHALL CONFORM TO S.C.D.O.T.
CATCH BASIN TYPE 16 AS SHOWN ON S.C.D.O.T. STANDARD DWG NO 719-016-01 & 719-016-02






STRUCTION

CON

DRAWN BY: JCM

FILE: 920-C400

SCALE: NONE






668 MARINA DRIVE SUITE B-1 CHARLESTON, S.C. 29492

PHONE: (843) 849-8945 FAX: (843) 849-8974 EMAIL: CSE@CIVILSITEENV.COM


920-PH2
SHEET NUMBER

CD-2

STORMDRAIN & WATER SERVICE CONFLICT DETAIL N.T.S.



SEWER SERVICE & STORMDRAIN CONFLICT DETAIL
N.T.S.



NOTE: ALL FIXTURES AND PIPE USED IN OFFSET TO BE DUCTILE IRON

VERTICAL OFFSET DETAIL

PHONE: (843) 849-8945 FAX: (843) 849-8974 EMAIL: CSE@CIVILSITEENV.COM


668 MARINA DRIVE SUITE B-1 CHARLESTON, S.C. 29492


CSE JOB NUMBER 920-PH2


DETAILS DETAILS DRAINAGE TRUCTION & SEWER 52ND

DRAWN BY: JCM FILE: 920-C400


SCALE: NONE DATE: 6-28-13




















SHRUB PLANTING DETAIL

GENERAL NOTES:

- 1. THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION BOTH HORIZONTALLY & VERTICALLY OF ALL EXISTING & PROPOSED UTILITIES BEFORE COMMENCING WORK, AND HE SHALL AGREE TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES. THE CONTRACTOR SHALL REPAIR ANY DAMAGE TO UTILITIES THAT ARE DISTURBED AS A RESULT OF THE WORK.
- 2. ALL AREAS THAT ARE DISTURBED BY CONSTRUCTION INSIDE OR OUTSIDE OF THE LIMIT OF WORK SHALL BE REPAIRED, GRADED AND GRASSED.
- 3. ALL TREES AND SHRUBS SHALL RECEIVE PINESTRAW MULCH AT A MINIMUM DEPTH OF 3".
- 4. PROVIDE EROSION CONTROL WHERE SLOPES ARE GREATER THAN 3:1 AND WHERE EROSION KEEPS RE-OCCURRING.
- 5. ALL TREE, SHRUB, AND GROUNDCOVER MATERIAL SHALL BE PLANTED WITHIN 24 HOURS OF DELIVERY.
- 6. ANY PLANTS LOCATED IN DIRECT SUN SHALL BE NURSERY SUN GROWN.
- 7. ALL PLANT MATERIAL TO MEET OR EXCEED AAN STANDARDS.
- 8. ALL TREES TO BE PLANTED FOLLOWING ACCEPTED HORTICULTURAL PRACTICES. PLANTING HOLES TO BE BACKFILLED WITH 1/3 COMPOST. DO NOT APPLY FERTILIZER AT PLANTING.
- 9. ALL SHRUBS TO BE SURFACE FERTILIZED WITH OSMOCOTE SLOW-RELEASE FERTILIZER ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.
- 10. CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL NECESSARY LICENSES AND INSURANCE TO COMPLETE WORK.
- 11. FINAL CLEANUP OF SITE AS A RESULT OF LANDSCAPE OPERATIONS AND ALL FINE GRADING SHALL BE THE RESPONSIBILITY OF THE LANDSCAPE CONTRACTOR.
- 12. CONTRACTOR SHALL ENSURE POSITIVE DRAINAGE.
- 13. ALL PLANT MATERIAL, WATERING BAGS, AND WORKMANSHIP TO BE GUARANTEED FOR ONE YEAR FROM THE DATE OF ACCEPTANCE BY THE OWNER OR OWNER'S REPRESENTATIVE.
- 14. CONTRACTOR TO MAINTAIN ALL PLANTBEDS AND PLANT LIFE UNTIL FINAL ACCEPTANCE OF LANDSCAPE. WARRANTY PERIOD OF ONE YEAR FOR PLANT MATERIALS BEGINS WHEN COMPLETION OF ALL PUNCH LIST ITEMS AND FINAL ACCEPTANCE OF LANDSCAPE HAVE BEEN APPROVED.
- 15. CONTRACTOR SHALL REPORT ANY DISCREPANCIES TO LANDSCAPE ARCHITECT PRIOR TO CONSTRUCTION.
- 16. STAKING ONLY REQUIRED AS DEEMED NECESSARY BY THE LANDSCAPE CONTRACTOR.
- 17. THERE SHALL BE NO SUBSTITUTIONS, DELETIONS, OR ADDITIONS WITHOUT WRITTEN APPROVAL OF THE LANDSCAPE ARCHITECT.
- 18. ALL CONSTRUCTION SHALL CONFORM TO COUNTY, STATE, AND FEDERAL REQUIREMENTS.

ABBRV.	QUAN.	BOTANICAL/COMMON	HEIGHT	CAL./CONT.	NOTEC
Evergreen			IILIGIII	CALI/CONT.	NOTES
ILEC	9	llex cassine / Dahoon Holly	6'-8'	В&В	Full natural Form; Strong central leader; Foliage to extend to ground
JUNV	6	Juniperus virginiana / Eastern Red Cedar	8'-10'	B&B	Full natural Form; Strong central leader; Foliage to extend to ground
MAGL	9	Magnolia grandiflora 'Little Gem' / Little Gem Magnolia	8'-10'	B&B	Full natural Form; Strong central leader; White flowers
Understor	y Trees / La	rge Shrubs:			
CALR	6	Callistemon rigidus / Bottlebrush Tree	5'-6'	30 gal.	Full natural Form; Containerized Material; Red flowers
ILLP	10	Illicium parviflorum / Anise	3'-4'	7 gal.	Full natural Form; Containerized Material

ABBREVIATION NOTE:

WHERE AN ABBREVIATION IS SHOWN, THE FOLLOWING NOTES APPLY: ABBRV - BOTANICAL ABBREVIATION.

QUAN - QUANTITY OF PLANT MATERIAL REQUIRED FOR THE PROJECT. (NOTE: CONTRACTOR RESPONSIBLE TO VERIFY QUANTITIES INDICATED. PLAN SHALL TAKE PRECEDENCE OVER SCHEDULE.) BOTANICAL/COMMON - PLANT MATERIAL TO BE INSTALLED.

CAL - CALIPER/DIAMETER OF TRUNK. (CALIPER SHALL TAKE PRECEDENCE OVER HEIGHT AND SPREAD.) CONT - CONTAINER TYPE WHICH PLANT MATERIAL IS ENCASED UPON SITE DELIVERY. (HEIGHT AND CALIPER SHALL TAKE PRECEDENCE OVER CONTAINER.)

NOTES - SPECIFIC NOTES FURTHER SPECIFYING OR DESCRIBING PLANT MATERIAL

QUANTITIES NOTES:

PLANT MATERIAL LIST WAS PREPARED FOR ESTIMATING PURPOSES ONLY. QUANTITY ESTIMATES HAVE BEEN MADE CAREFULLY, BUT THE LANDSCAPE ARCHITECT ASSUMES NO LIABILITY FOR OMISSIONS OR ERRORS. CONTRACTORS SHALL MAKE THEIR OWN QUANTITY TAKE-OFFS USING DRAWINGS TO DETERMINE QUANTITIES TO THEIR SATISFACTION, REPORTING PROMPTLY TO THE LANDSCAPE ARCHITECT ANY DISCREPANCIES WHICH MAY AFFECT BIDDING AND/OR INSTALLATION. NO EXTRA COMPENSATION SHALL BE ALLOWED FOR EXTRA QUANTITIES NECESSARY TO COMPLETE THE WORK.


TREEGATOR BAG NOTE:

FOR ALL TREES AND SHRUBS, CONTRACTOR SHALL PROVIDE TREEGATOR BAGS OR COMPARABLE WATERING SYSTEM AT THE QUANTITIES BELOW TO BE ADEQUATELY MAINTAINED FOR THE DURATION OF THE ONE YEAR ESTABLISHMENT PERIOD. ALL TREES SHALL BE WATERED ACCORDING TO THE FOLLOWING SCHEDULE:

FLOW RATE: ROUGHLY 2.5 GPH DEPENDING ON SOIL TYPE AND TEMP. RECOMMENDED 10 GALLOON CAPACITY PER CALIPER INCH.

RECOMMENDED FILL RATE BY CALIPER INCHES FOR STANDARD 20 GALLON CAPACITY BAGS:

1-2 INCH: 1 FILL/WEEK 3-4 INCH: 2 FILLS/WEEK 4-5 INCH (DOUBLE BAG): 1 FILL / WEEK 5-8 INCH (DOUBLE BAG): 2 FILLS / WEEK



SURCULUS


Know what's below. Call before you dig.

52ND

DRAWN BY: EFS FILE: 920-PH2-C200 SCALE: N/A

DATE: 05-25-17

CAROL I



CSE JOB NUMBER 920-PH2 SHEET NUMBER